

AD-A069 907

NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/2  
NATIONAL DAM SAFETY PROGRAM. BREAKNECK DAM (NJ-00425), DELAWARE--ETC(U)  
MAY 79 R J McDERMOTT

















DACW61-78-C-0124

UNCLASSIFIED

NL

1 OF 2

AD  
A069907







**LEVEL**

DELAWARE RIVER BASIN  
TRIBUTARY TO HAYNES CREEK  
BURLINGTON COUNTY  
NEW JERSEY

**A069907**

# **BREAKNECK DAM**

## **NJ 00425**

**PHASE 1 INSPECTION REPORT**  
**NATIONAL DAM SAFETY PROGRAM**

**DDC FILE COPY**



Approved for public release;  
distribution unlimited

**DEPARTMENT OF THE ARMY**

Philadelphia District  
Corps of Engineers  
Philadelphia, Pennsylvania

May, 1979

DDC  
RECEIVED  
JUN 15 1979  
REGISTERED

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DDC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00425	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Breakneck Dam Burlington County, N.J.	5. TYPE OF REPORT & PERIOD COVERED (9) FINAL rept.	
7. AUTHOR(s) 10 Richard J. McDermott, P.E.	6. PERFORMING ORG. REPORT NUMBER	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Storch Engineering 220 Ridgedale Ave. Florham Park, N.J. 07932	8. CONTRACT OR GRANT NUMBER(s) 15 DACW61-78-C-0124	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 12 150A	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 6 National Dam Safety Program. Breakneck Dam (NJ-00425), Delaware River Basin, Tributary to Haynes Creek, Burlington County, New Jersey. Phase I Inspection Report.	12. REPORT DATE 11 May 1979	
16. Report. Approved for public release; distribution unlimited.	13. NUMBER OF PAGES 100	
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)	15. SECURITY CLASS. (of this report) Unclassified	
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Visual Inspection Spillways National Dam Inspection Act Report Structural Analysis Breakneck Dam, N.J. Embankments		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

**NOTICE**

**THIS DOCUMENT HAS BEEN REPRODUCED  
FROM THE BEST COPY FURNISHED US BY  
THE SPONSORING AGENCY. ALTHOUGH IT  
IS RECOGNIZED THAT CERTAIN PORTIONS  
ARE ILLEGIBLE, IT IS BEING RELEASED  
IN THE INTEREST OF MAKING AVAILABLE  
AS MUCH INFORMATION AS POSSIBLE.**





IN REPLY REFER TO

**NAPEN-D**

**DEPARTMENT OF THE ARMY  
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS  
CUSTOM HOUSE-2 D & CHESTNUT STREETS  
PHILADELPHIA, PENNSYLVANIA 19106**

**Honorable Brendan T. Byrne  
Governor of New Jersey  
Trenton, New Jersey 08621**

**29 MAY 1979**

**Dear Governor Byrne:**

**Inclosed is the Phase I Inspection Report for Breakneck Dam in Burlington County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.**

**Based on visual inspection, available records, calculations and past operational performance, Breakneck Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillways are considered inadequate since 63 percent of the Spillway Design Flood -SDF- would overtop the dam. The SDF, in this instance, is one half of the Probable Maximum Flood (PMF). To insure adequacy of the structure, the following actions, as a minimum, are recommended:**

**a. The spillways adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillways and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system, should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.**

**b. Within six months from the date of approval of this report, engineering studies and analyses should be initiated to determine the dam's embankment condition and structural stability. This should include test borings to determine material properties relative to stability and seepage. A topographic survey of the dam and vicinity should be made. Any remedial measures found necessary should be initiated with calendar year 1980.**

NAPEN-D

Honorable Brendan T. Byrne

c. The following remedial actions should be completed within six months from the date of approval of this report:

(1) All trees and brush on the earthfill embankment should be cut off at ground level and removed with minimal disturbance of the embankment surface.

(2) Eroded areas and bare areas should be filled and stabilized with ground cover vegetation. Positive drainage should be provided along the crest road.

(3) The submerged portions of the spillway and inaccessible portions of the discharge culverts should be inspected for distress and deterioration with the lake drawn down. Concrete surfaces should be repaired as necessary.

(4) Debris accumulated in the outlet works and around the spillways should be removed.

(5) Seepage areas should be monitored periodically so that the rate and source can be determined.

d. The owner of the dam should initiate a formal program of annual inspection and maintenance with special attention given to the culvert joint. The observations and measurements should be recorded on standardized checklist forms. Inspection checklists and complete records of maintenance should be included in a permanent file. Repairs should be performed as required and the following maintenance should be performed annually: remove brush and trees from the embankment, fill and stabilize eroded and bare areas, clear debris from the spillway openings and the downstream channel, point deteriorated sections of the brick arch discharge culvert and seal the joint between the culvert sections.

e. The lake should be drained at least once every five years to permit a complete inspection and repair of the dam and appurtenances.

f. The downstream toe of the embankment should be thoroughly inspected with the downstream lake level drawn down. This area should be thoroughly investigated for seepage and animal burrows, especially in the area of the corrugated metal pipe arch outfall and the undercut bank of the natural channels.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist <input checked="checked" type="checkbox"/>	Avail and/or special

**NAPEN-D**


**Honorable Brendan T. Byrne**

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Edwin B. Forsythe of the Sixth District. Under the provisions of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



**JAMES G. TON**  
Colonel, Corps of Engineers  
District Engineer

1 Incl  
As stated

Copies furnished:  
Dirk C. Hofman, P.E., Deputy Director  
Division of Water Resources  
N. J. Dept. of Environmental Protection  
P. O. Box CN029  
Trenton, NJ 08625

John O'Dowd, Acting Chief  
Bureau of Flood Plain Management  
Division of Water Resources  
N. J. Dept. of Environmental Protection  
P. O. Box CN029  
Trenton, NJ 08625

BREAKNECK DAM (NJ00425)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 19 December 1978 by Storch Engineers under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Breakneck Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillways are considered inadequate since 63 percent of the Spillway Design Flood -SDF- would overtop the dam. The SDF, in this instance, is one half of the Probable Maximum Flood (PMF). To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillways adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillways and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system, should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.

b. Within six months from the date of approval of this report, engineering studies and analyses should be initiated to determine the dam's embankment condition and structural stability. This should include test borings to determine material properties relative to stability and seepage. A topographic survey of the dam and vicinity should be made. Any remedial measures found necessary should be initiated with calendar year 1980.

c. The following remedial actions should be completed within six months from the date of approval of this report:

(1) All trees and brush on the earthfill embankment should be cut off at ground level and removed with minimal disturbance of the embankment surface.

(2) Eroded areas and bare areas should be filled and stabilized with ground cover vegetation. Positive drainage should be provided along the crest road.



(3) The submerged portions of the spillway and inaccessible portions of the discharge culverts should be inspected for distress and deterioration with the lake drawn down. Concrete surfaces should be repaired as necessary.

(4) Debris accumulated in the outlet works and around the spillways should be removed.

(5) Seepage areas should be monitored periodically so that the rate and source can be determined.

d. The owner of the dam should initiate a formal program of annual inspection and maintenance with special attention given to the culvert joint. The observations and measurements should be recorded on standardized checklist forms. Inspection checklists and complete records of maintenance should be included in a permanent file. Repairs should be performed as required and the following maintenance should be performed annually: remove brush and trees from the embankment, fill and stabilize eroded and bare areas, clear debris from the spillway openings and the downstream channel, point deteriorated sections of the brick arch discharge culvert and seal the joint between the culvert sections.

e. The lake should be drained at least once every five years to permit a complete inspection and repair of the dam and appurtenances.

f. The downstream toe of the embankment should be thoroughly inspected with the downstream lake level drawn down. This area should be thoroughly investigated for seepage and animal burrows, especially in the area of the corrugated metal pipe arch outfall and the undercut bank of the natural channels.

APPROVED:

  
JAMES G. TON

Colonel, Corps of Engineers  
District Engineer

DATE:

29 May 1979

PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Breakneck Dam, I.D. NJ00425
State Located:	New Jersey
County Located:	Burlington
Drainage Basin:	Delaware River
Stream:	Tributary to Haynes Creek
Date of Inspection:	December 19, 1979

Assessment of General Condition of Dam

Breakneck Dam is in fair overall condition and outwardly structurally stable, however, the hydraulic capacity of the spillways are inadequate. The SDF (Spillway Design Flood) for Breakneck Dam is 1/2 PMF. The spillways at the dam are capable of passing about 31 percent of the PMF (62 percent of the SDF) without overtopping the dam.

The owner should engage a qualified professional engineer soon to perform more accurate hydraulic and hydrologic analyses of the spillways, the downstream channel and the contributing watershed. Based on the findings of these analyses, the dam and spillways should be modified to accommodate a storm equivalent to the SDF without an overtopping of the dam.

It is recommended that the following remedial measures be undertaken by the owner in the near future:

1. All trees and brush on the earthfill embankment should be cut off at ground level and removed with minimal disturbance of the embankment surface.
2. Eroded areas and bare areas should be filled and stabilized with ground cover vegetation in the near future. Positive drainage should be provided along the crest road.

3. The submerged portions of the spillway and inaccessible portions of the discharge culverts should be inspected for distress and deterioration with the lake drawn down.

Concrete surfaces in the spillways should be sand blasted and coated with an epoxy sealant after all cracks are carefully inspected and pressure grouted.

4. Debris accumulated in the outlet works and around the spillways should be removed.
5. Seepage area should be monitored periodically so that the rate and source can be determined.


The owner of the dam should initiate a formal program of annual inspection and maintenance with special attention given to the culvert joint. The inspections should be performed by a qualified professional engineer and the observations and measurements should be recorded on standardized check-list forms. Inspection check-lists and complete records of maintenance should be included in a permanent file, available for public inspection.

Repairs should be performed as required and the following maintenance should be performed annually: remove brush and trees from the embankment, fill and stabilize eroded and bare areas, clear debris from the spillway openings and the downstream channel, point deteriorated sections of the brick arch discharge culvert and seal the joint between the culvert sections.

Furthermore, the lake should be drained at least once every five years to permit a complete inspection and repair of the dam and appurtenances.

A qualified professional engineer should be engaged in the near future to perform a comprehensive dam stability analysis with special attention given to the area along the corrugated metal pipe arch and the culvert joint. A Topographic survey, borings, test probes and seepage pressure evaluations should be performed as part of the stability analysis, and typical soil sections for the embankment should be developed along originally constructed areas, along the culverts, along areas that have undergone substantial filling since the 1940 repairs and along suspected seepage paths. Seepage and steepness of side slopes should be reviewed carefully with respect to the typical dam sections developed.

In addition, the downstream toe of the embankment should be thoroughly inspected with the downstream lake level drawn down. This area should be thoroughly investigated for seepage and animal burrows, especially in the area of the corrugated metal pipe arch outfall and the undercut bank of the natural channels.

A handwritten signature in cursive script, reading "Richard J. McDermott". The signature is written in dark ink and is positioned above the printed name.

Richard J. McDermott, P.E.



OVERVIEW PHOTO - BREAKNECK DAM

19 DEC. 1978



## TABLE OF CONTENTS

	<u>Page</u>
ASSESSMENT OF GENERAL CONDITION OF DAM	i
OVERVIEW PHOTO	iv
TABLE OF CONTENTS	v
PREFACE	vii
SECTION 1 - PROJECT INFORMATION	1
1.1 General	
1.2 Description of Project	
1.3 Pertinent Data	
SECTION 2 - ENGINEERING DATA	11
2.1 Design	
2.2 Construction	
2.3 Operation	
2.4 Evaluation	
SECTION 3 - VISUAL INSPECTION	15
3.1 Findings	
SECTION 4 - OPERATIONAL PROCEDURES	19
4.1 Procedures	
4.2 Maintenance of Dam	
4.3 Maintenance of Operating Facilities	
4.4 Description of Warning System	
4.5 Evaluation of Operational Adequacy	

TABLE OF CONTENTS (cont.)

	<u>Page</u>
SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1 Evaluation of Features	22
SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	26
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS	
7.1 Dam Assessment	
7.2 Recommendations	29
PLATES	
1 KEY MAP	
2 VICINITY MAP	
3 SOIL MAP	
4 TOPOGRAPHICAL MAP	
5 GENERAL PLAN	
6 PRIMARY SPILLWAY	
7 SECONDARY SPILLWAY	
8 SECTION 4-A	
9 PHOTO LOCATION PLAN	
APPENDICES	
1 Check List - Visual Inspection	
Check List - Engineering Data	
2 Photographs	
3 Engineering Data	
4 Hydrologic Computations	
5 Bibliography	

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 30214. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that the unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.



PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

BREAKNECK DAM I.D. NJ00425

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The Division of Water Resources of the New Jersey Department of Environmental Protection (NJDEP) in cooperation with the Philadelphia District of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the State of New Jersey. Storch Engineers has been retained by the NJDEP to inspect and report on a selected group of these dams. The NJDEP is under agreement with the Philadelphia District of the Corps of Engineers.

b. Purpose of Inspection

Breakneck Dam was inspected on December 19, 1978 to generally assess the structural integrity and operational adequacy of the dam and appurtenances.

## 1.2 Description of Project

### a. Description of Dam and Appurtenances

The facilities at Breakneck Dam consist of an earthfill embankment with two concrete box drop inlet spillways. (see Plate 5, Overview Photo and Photos 1 and 3) The spillways discharge into culverts that pass through the embankment and outfall at the downstream toe of the embankment (see Photos 2 and 4).

The earthfill embankment is approximately 255 feet long and extends east/west. The embankment crest is 33 feet wide with an asphalt roadway at its center, about 21 feet wide (see Plate 8 and Photo 6). Based on field measurements, the upstream and downstream slopes are approximately 1:1 (see Photo 5). The embankment crest is generally level at elevation 55.8 (MSL) and the dam is about 14 feet high. Dense vegetation consisting of low level ground cover, brush and trees, covers both the upstream and downstream slopes of the embankment. The surface soil on the embankment consists mainly of sand.

The primary spillway is located about 90 feet west of the east end of the embankment. The spillway has a total crest length of 43 feet. The spillway crest is at elevation 51.0 and is about 4.8 feet below the dam crest.

The primary spillway structure consists of three reinforced concrete walls with spread footings set on 6 inch diameter timber piles 6 to 8 feet long. The downstream wall is formed by a rubble masonry headwall at the upstream end of the brick arch culvert. The center portion of the floor slab, between the wall footings is a separate member poured at grade with

eight 2-inch diameter weep holes to relieve uplift pressure. A timber tongue and groove sheet pile cutoff wall is located around the outside of the piles below the wall footings. A horizontal reinforced concrete strut is located at the downstream end of the structure between the tops of the two side walls to resist unbalanced hydrostatic thrust.

The primary spillway originally had one outlet works consisting of a 15" x 15" manual slide gate which reportedly has been replaced with a larger gate. The size of the replacement gate is uncertain.

The discharge culvert for the primary spillway consists of a brick arch extending through the embankment about two thirds of its width. At this point, the brick arch joins a corrugated metal pipe arch extension that continues through the embankment to a reinforced concrete headwall with wing walls at the downstream toe of the embankment.

The secondary spillway is located about 45 feet east of the west end of the embankment. The spillway has a total crest length of 14 feet, 2.5 feet controlled with timber stoplogs and 11.5 feet uncontrolled (inlet side walls). The normal stoplog crest is at elevation 50.6 and is about 5.2 feet below the dam crest. The inlet sidewall crest is at elevation 51.2 and is about 4.6 feet below the dam crest.

The secondary spillway structure consists of reinforced concrete side walls with slotted returns on the upstream face, where the timber stoplogs are fitted. The discharge culverts for the spillway consist of two 36-inch diameter corrugated metal pipes that outfall at the downstream embankment toe through a reinforced concrete headwall.

b. Location

Breakneck Dam impounds Taunton Lake and is located in the Township of Medford, Burlington County, New Jersey (see Plates 1 and 2). Discharge from Taunton Lake passes through the spillways at Breakneck Dam and along a short natural channel into Lake Pine, a tributary of Haynes Creek (See Plate 4 ). Taunton Lake is immediately downstream of Centennial Lake Dam. There are also a number of additional lakes with dams further upstream.

c. Size and Hazard Classification

Size and hazard classification criteria presented in "Recommended Guidelines for Safety Inspection of Dams," published by the U. S. Army Corps of Engineers are as follows:

SIZE CLASSIFICATION

IMPOUNDMENT

<u>Category</u>	<u>Storage (Ac-Ft)</u>	<u>Height (Ft)</u>
Small	$<1000$ and $\geq 50$	$<40$ and $\geq 25$
Intermediate	$\geq 1000$ and $<50,000$	$\geq 40$ and $<100$
Large	$\geq 50,000$	$\geq 100$

HAZARD POTENTIAL CLASSIFICATION

<u>Category</u>	<u>Loss of Life</u> (Extent of Development)	<u>Economic Loss</u> (Extent of Development)
Low	None expected (No permanent structures for human habitation)	Minimal (Undeveloped to occasional structures or agriculture)

Significant	Few (No urban developments and no more than a small number of inhabitable structures)	Appreciable (Notable agriculture, industry or structures)
High	More than few	Excessive (Extensive community, industry or agriculture)

The characteristics of Breakneck Dam are:

Storage = 354 acre-feet (at top of dam)

Height ---= 14 feet

Potential Loss of Life: Approroximately 15 residential dwellings in the downstream SDF flood plain along Lake Pine.

Potential Economic Loss: Flooding of residential development in the downstream area.

Therefore, Breakneck Dam is classified as "small" size with "high" hazard potential.

d. Ownership

Breakneck Dam is owned by the Taunton Lake Company, Taunton Lake, Marlton P.O., New Jersey 08053.

e. Purpose of the Dam

The purpose stated on the 1940 "Application for Permit for Repair or Construction of Dams" is Private Real estate Development. Now that the lake shore properties have been developed, the dam serves to impound a recreational lake.



f. Design and Construction History

Reportedly the original embankment and spillway were constructed around 1870. The earthfill embankment and the brick arch culvert basically have remained unchanged since the original construction. The spillway was originally a timber frame structure with timber stoplogs.

In September 1940, the dam was breached and a substantial portion of the embankment was lost, but the brick arch culvert remained intact. Reports of damage in the downstream area were not available. Repairs were designed and implemented. The breach was filled and a new reinforced concrete box drop inlet spillway was constructed at the upstream end of the brick arch. The contractor was reportedly Hill Construction Company of Mount Holly, New Jersey.

Since the 1940 repair work, there have been two major changes in the facility. A corrugated metal pipe arch and concrete headwall were added to the downstream end of the brick arch and a secondary spillway consisting of a reinforced concrete drop inlet with two 36-inch diameter discharge culverts and downstream concrete headwall were constructed.

g. Normal Operational Procedure

The operation of the spillway facilities at Breakneck Dam is coordinated by and for the most part performed by the Civil Defense Director of the Township of Medford.

Maintenance of Breakneck Dam is usually performed "as-needed" by the Burlington County Road Department or the Township of Medford, in cooperation with the owner. Regular maintenance

consists of the following: 1) lowering the water level each spring to permit repair of docks, cleaning of beaches and inspection and repair of the dam and appurtenances. Occasionally fill and sod are placed on the embankment slopes to restore and stabilize eroded areas.

### 1.3 Pertinent Data

- a. Drainage Area - 13.0 square miles
- b. Discharge at Damsite

Maximum known flood at damsite	Dam breached in 1940
Outlet works at normal pool elevation	22 cfs
Diversion tunnel low pool outlet at pool elevation	N.A.
Diversion tunnel outlet at pool elevation	N.A.
Gated spillway capacity at normal pool elevation	2 cfs
Gated spillway capacity at top of dam (Secondary)	196 cfs
Ungated spillway capacity at top of dam (Primary)	1102 cfs
Total spillway capacity at top of dam	1298 cfs

- c. Elevation (Feet above MSL)

Top of Dam	55.8
Maximum pool-design surcharge	57.4
Full flood control pool	N.A.

Recreation pool	51.0
Spillway crest	51.0
Upstream portal invert diversion tunnel	N.A.
Stream bed at centerline of dam	41.6
Maximum tailwater	50.0 (Estimated)

d. Reservoir

Length of maximum pool	4100 feet
Length of recreation pool	4200 feet
Length of flood control pool	N.A.

e. Storage (Acre-feet)

Recreation pool	125 acre-feet
Flood control pool	N.A.
Design surcharge	451 acre-feet
Top of dam	354 acre-feet

f. Reservoir Surface (Acres)

Top of dam	60 acres (estimated)
Maximum pool	67 acres (estimated)
Flood control pool	N.A.
Recreation pool	39 acres
Spillway crest	39 acres

g. Dam

Type	Earthfill
Length	255 feet
Height	14 feet



Sideslopes - Upstream	1 horiz. to 1 vert.
- Downstream	1 horiz. to 1 vert.
Zoning	Unknown
Impervious core	Unknown
Cutoff	Unknown
Grout curtain	Unknown
h. Diversion and Regulating Tunnel	N.A.
i. Primary Spillway	
Type	Drop Inlet
Length of weir	43 feet
Crest elevation	51.0
Gate	Manual Slide Gate, 15" x 15"
Upstream channel	N.A.
Downstream channel	Discharge culvert (Brick arch and CMPA)
j. Secondary Spillway	
Type	Drop Inlet
Length of weir	14.0 feet
Crest elevation	50.6 feet (Stoplogs) 51.2 feet (Concrete Walls)
Gate	None
Upstream	N.A.
Downstream	Discharge culvert (2-36" diameter CMP's)

k. Regulating Outlets

Manual slide gate

Gate opening 15" x 15" in  
Primary Spillway. Reportedly  
replaced with larger gate,  
however no size informa-  
tion available.

## SECTION 2: ENGINEERING DATA

### 2.1 Design

Neither plans nor calculations are available for the original construction of Breakneck Dam or appurtenances. Design calculations and a construction plan for the hydraulic capacity, structure and foundation of the primary spillway prepared in 1940 are contained in the NJDEP file.

Neither plans nor calculations are available for either the secondary spillway or the corrugated metal pipe arch extension of the primary spillway discharge culvert.

### 2.2 Construction

There are no records available in the NJDEP file for the original construction of the dam.

Five dam inspection reports in the NJDEP file, deal with repair of the dam after it was breached in September 1940. A summary of these reports follows:

Report dated September 4, 1940:

Prepared by J. C. King, N.J. State Water Policy Commission (NJSWPC)  
Breach caused by storm of September 1, 1940, verified.

Report dated September 26, 1940:

Prepared by J. M. Brooks, NJSWPC

Exposed brick arch culvert inspected and found to be in good condition and adequate for reuse in repair of dam.

Report dated December 26, 1940:

Prepared by J. C. King, NJSWPC

Footings for primary spillway completed. Breach filled to about halfway from west end of the opening.

A large gate valve was recommended, 24" x 24".

Report dated January 8, 1941:

Prepared by J. C. King, NJSWPC

Reinforcing revisions in the drop inlet walls and the horizontal strut were agreed upon.

Report dated February 7, 1941:

Prepared by J. C. King, NJSWPC

Primary spillway construction completed. Upstream brick arch headwall was cut down to match the top of the spillway. As-built spillway crest length was longer than approved, therefore, the required operating head and consequently the elevation of the dam crest were reduced. Pointing of stone work in the brick arch, filling of the washout and turfing of the embankment slopes were completed in accordance with the drawings. Acceptance of the repair work was recommended.

There are no records available in the NJDEP file for the construction of the secondary spillway or the corrugated metal pipe arch extension of the primary spillway discharge culvert.

### 2.3 Operation

No formal records of the operation of the dam have been kept by the owner.

Generally the lake is drawn down a few feet in early spring each year to permit shoreline residents to repair docks and clean beaches. Periodically the lake is completely drawndown to facilitate inspection of the dam and appurtenances.

Reportedly, complete drawdown of the lake takes about one day.

The lake level is monitored periodically. The slide gate on the primary spillway and the stoplogs on the secondary spillway are adjusted so as to maintain the desired water level in the lake. The lake is usually lowered about 6 inches in anticipation of intense storms.

In January 1971, the owner of the dam, Taunton Lake Company engaged Theodore A. Shaw, PE to perform an "Annual Inspection" of the dam. This report is contained in the NJDEP file. The dam was reported to have been generally in good condition. Repairs were suggested, consisting of: 1) Placing riprap beneath the secondary spillway outlet, 2) inspecting and pointing the interior of the brick arch.

## 2.4 Evaluation

### a. Availability

Engineering information for the original dam, the secondary spillway and the corrugated metal pipe arch extension of the discharge culvert is not available.

Hydraulic and structural calculations and construction drawings for the primary spillway structure are available from the NJDEP file. Inspection reports for the dam, prepared by NJSWPC describing conditions at the dam during the period from the breach in 1940 to completion of repairs in 1941 are also in the NJDEP file. This information is available for inspection at the offices of the Bureau of Flood Plain Management, 1474 Prospect Street, Trenton, N. J.

b. Adequacy

Engineering data available in the NJDEP file are adequate to permit an assessment of the hydraulic capacity of the primary spillway, but are not of significant value in performing a hydraulic capacity of the secondary spillway nor the structural stability of the dam and the primary spillway.

c. Validity

Based on the findings of the field inspection, the information contained in the NJDEP file for Breakneck Dam is essentially accurate with respect to the as-built conditions at the site.



## SECTION 3: VISUAL INSPECTION

### 3.1 Findings

#### a. General

Breakneck Dam was inspected on December 19, 1978 by members of the staff of Storch Engineers. A copy of the visual inspection check list is contained in Appendix 1. The following procedures were employed for the inspection:

1. The embankment of the dam, appurtenant structures and adjacent areas were examined.
2. Areas of suspected seepage were noted and located.
3. The embankment and accessible appurtenant structures were measured and key elevations were determined by hand level.
4. The embankment and appurtenant structures and adjacent areas were photographed.

Information presented in the following portions of this Section consists of observations made during the field inspection.

#### b. Dam

The embankment crest was generally level with a straight horizontal alignment leading to a slight northward curve at the east end. The paved crest road and adjoining areas were in good condition with slight erosion along the top of the side slopes from poor road drainage.

Most of the upstream and downstream slopes were covered with extensive tree and brush growth, and sparse grass. One area of significant road drainage related erosion was located on

the downstream slope, adjacent to the primary spillway discharge culvert. Minor erosion was noted in several other areas along both side slopes.

A stilling basin was observed at the outfall of the secondary spillway discharge culvert. The west bank of the natural channel downstream of this outfall has been undercut and eroded. Seepage was noted exiting from the undercut area (see Plate 5 and Photo 9) discharging as a trickle with some suspended orange silt.

No evidence of cracking, settling or animal burrows was noted along the embankment.

Generally, soils at the dam site are composed of unconsolidated stratified silty sand and narrowly graded sand of marine origin. These deposits, known as Kirkwood Sands, were formed during the Tertiary Period and extend for a considerable depth. The lake basin contains significant surficial organic matter, silt and sand with some clay. Bedrock is more than 100 feet below the surface.

c. Appurtenant Structures

Spillways

The exposed portions of both concrete spillways generally were in good condition with exposed aggregate on the concrete surfaces. The submerged and buried portions were not inspected.

The tops of both spillways were open and readily accessible, constituting a serious physical safety hazard.



### Outlet Works

The outlet works for the dam consisting of a manual slide gate is located on the south wall of the primary spillway in the southwest corner of the structure. Discharge from the slide gate passes directly into the spillway. The gate wheel is accessed by a steel frame and timber plank walkway.

The upper portion of the slide gate mechanism, consisting of the gate wheel and stem, was in good condition. The gate was submerged and could not be inspected. At the time of the inspection the gate was closed.

### Discharge Culverts

The discharge culvert for the primary spillway consists of a brick arch, 13.8 feet wide and 7.8 feet high (upstream) and a corrugated metal pipe arch (downstream). This culvert was apparently in fair condition. The interior of the culvert could not be inspected in detail because it was not accessible. Mortar was missing from brick joints at the upstream end of the culvert. The downstream concrete headwall was in good condition. The discharge culvert of the secondary spillway, consists of two 36-inch diameter corrugated metal pipes, which were apparently in good condition. Both the upstream and downstream concrete headwalls were in good condition. At the downstream end of the culvert there is a stilling basin with the remains of a riprap apron along the perimeter of the basin, which apparently has been scoured away.

#### d. Reservoir Area

Taunton Lake is about 4100 feet long and varies in width from about 200 feet to about 500 feet.

The immediate shore line contains residential development. The area surrounding the lake slopes gradually upward away from the lake at slopes of between 3% and 10% in the immediate shoreline area. Numerous docks and several small community beaches were observed along the shoreline.

e. Downstream Channel

The downstream channel at Breakneck Dam consists of two natural streams which join a short distance downstream and have no significant obstructions. Both natural channels share the same flood plain, which is flat and broad with substantial vegetation in the form of trees and brush.

## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

The water level in Taunton Lake is normally naturally controlled by overflow through the spillways. The lake level is lowered several inches in anticipation of intense storms by Township of Medford officials. During these periods the lake level is observed frequently and stoplogs on the secondary spillway and the gate on the primary spillway are used to augment outflow. These activities are coordinated with upstream and downstream lakes so as to accommodate high discharges from one lake to another.

### 4.2 Maintenance of the Dam

There is no regular maintenance or inspection procedures for the dam and appurtenances. Maintenance is performed "as-needed" by the Burlington County Road Department and the Township of Medford in cooperation with the owner. Overall conditions at the dam are observed by local officials at least weekly. Occasional comprehensive inspections are made during periods when the lake is completely drawn down.

There has been no maintenance documentation for the dam. However, verbal accounts indicate almost annual repairs to the crest road and side slopes consisting of filling of road drainage related erosion, and placing of sod on the side slopes.

Past experience has shown that the joint between the brick arch culvert and corrugated metal pipe arch is an area of potential weakness. Differential movement and loss of soil from above the culvert has been experienced and large holes in the embankment

crest and the road have developed. Repairs have consisted of patching the joint with mortar and filling holes and depressions with locally available soil.

Judging from the present condition of the dam, maintenance has been adequate.

#### 4.3 Maintenance of Operating Facilities

Maintenance records for the spillways are not available. Reportedly the spillways have not been maintained recently. Occasionally stoplogs in the secondary spillway are replaced and the manual slide gate in the primary spillway is serviced. Reportedly the existing slide gate in the primary spillway is larger than the 15" x 15" gate indicated on the 1940 repair drawings. However, there is no record of the replacement of the gate nor the size of the new gate.

Maintenance records for the discharge culverts are poor. The NJDEP file indicates one formal inspection by T. A. Shaw, PE and subsequent recommendation consisting of constructing a riprap apron at the outfall of the secondary spillway and pointing the brick arch.

#### 4.4 Description of Warning System

The warning system for Breakneck Dam consists of frequent observation of the lake level by the Civil Defense Director, as often as hourly during intensive storms and close coordination with upstream and downstream dams. This procedure is not written, but has been established through long past experience of municipal officials.

The system was found to be inadequate at one time in the recent past. In 1958 an intense storm caused the dam at Marlton Lakes

(upstream) to breach. This dam is not in the Township of Medford and is not monitored by the above system. The breach outflow from Marlton Lakes caused dams at Packowango, the Girl Scout Camp and Bradocks Mill to breach. The flood flow was contained at Centennial Lake Dam immediately upstream of Taunton Lake.

#### 4.5 Evaluation of Operational Adequacy

The dam and appurtenances at Breakneck Dam have performed satisfactorily since the 1940 repair with no overtopping nor breaching.

There has been poor maintenance documentation, although maintenance apparently has been adequate to sustain the earthfill embankment and appurtenances.

The informal warning system that has been developed over the years has served adequately since 1958. However, it probably would not be adequate, should the SDF for Breakneck Dam occur.



## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design Data

Size and hazard classification were used in conjunction with "Recommended Guidelines for Safety Inspection of Dams" published by the U.S. Army Corps of Engineers to establish the SDF (Spillway Design Flood) for Breakneck Dam. The appropriate design range for this facility is 1/2 PMF to PMF (Probable Maximum Flood). Since the characteristics of Breakneck Dam as described in Section 1, fall into the lower end of the prescribed classification range, 1/2 PMF is used as the SDF.

The inflow hydrograph consists of a combination of runoff from the 5.7 square mile drainage area that inflows directly into Taunton Lake and the outflow hydrograph for Centennial Lake Dam immediately upstream (see HEC-1-DB Computations, Appendix 4). It has been assumed for this analysis that the SDF for Breakneck Dam would not breach Centennial Lake Dam. Therefore, discharge into Taunton Lake from Centennial Lake Dam would consist of spillway discharge and overtopping of Centennial Lake Dam.

Clark's Method with a synthetic time-area curve was used to analyze the drainage areas. General hydrologic characteristics such as: Drainage Area (DA), Surface Storage Index ( $S_t$ ), Main Channel Slope (S) and Man-made Impervious Cover Index (I) were computed using USGS quadrangles and aerial photographs. These data were used in conjunction with the following equations to determine the Clark's Method Parameters (R and Tc):

$$\begin{aligned} R/Tc + R &= 0.76 \\ Tc + R &= (DA/S)^{0.22} (S_t)^{0.35} (1 + 0.3I)^{-0.28} \end{aligned}$$

The total drainage area contributing to Taunton Lake is 13 square miles. Most of the watershed is undeveloped woodland and swamp with considerable residential development along the shoreline. Reservoir storage capacities were estimated using available data and surface areas measured from USGS quadrangles.

Discharge hydraulics for Breakneck Dam were established by evaluating the spillway crest lengths as a sharp-crested weir.

The SDF inflow hydrograph for Breakneck was routed through the spillways using the HEC-1-DB Computer Program, which indicated that the dam would be overtopped. Based on the depth of overtopping that would develop, it is probable that the dam would be breached. Computations show that overtopping in a non-breach condition would occur for about 25 hours with a maximum flow height of 1.58 feet above the dam crest and a maximum discharge of about 2772 cfs. It was also calculated that the existing spillways are adequate for a maximum flow of about 31 percent of the PMF without overtopping the dam (62 percent of the SDF).

The SDF routing discussed above does not include discharge through the slide gate or the stoplog controlled opening. The added use of these facilities would not alleviate overtopping potential.

b. Experience Data

Reportedly, Breakneck Dam has not been overtopped or breached since repairs were effected after the September 1940 washout.

Municipal Officials in the Township of Medford reportedly maintain vigilant monitoring of water surfaces in the township

during storm periods and control spillway facilities through declared emergencies. In 1958 four upstream dams were breached when the Marlton Lakes Dam breached. The progressive failure was halted at Centennial Lake Dam through careful use of the spillway and outlet works.

c. Visual Observation

At the time of the field inspection there was no evidence of past overtopping. Eroded areas were noted on the embankment side slopes which were apparently due to poor crest road drainage.

Based on field measurements the primary spillway is essentially as indicated on the drawings in the NJDEP file. The secondary spillway and the discharge culverts were measured to permit evaluation of discharge capacities.

d. Overtopping Potential

As noted above, the SDF for Breakneck Dam would result in overtopping of the dam for about 25 hours with a maximum flow height of 1.58 feet in a non-breach condition. Further calculations indicate that storms greater than 31 percent of the PMF would result in overtopping of the dam.

Considering the type of construction (earthfill embankment) and the magnitude of overtopping that would be associated with the SDF, the dam would probably be breached.

Projected breach conditions for Breakneck Dam were analyzed with the HEC-1-DB computer program. It was assumed that a breach would result in the loss of about 40 percent of the

dam crest length and would take about one hour to develop.

The tailwater conditions in Lake Pine (downstream) would limit the breach depth. It was estimated that the minimum bottom elevation of the breach would be about elevation 46.0. The peak breach discharge would be approximately 5717 cfs. The Breakneck Dam breach condition would result in a downstream SDF stage about 2.1 feet above the non-breach stage. This additional rise would occur over a period of about 1.5 hours and probably would not result in a significant increase in the potential for loss of life in the downstream area.

It should be noted that this analysis does not consider the breaching of Centennial Lake Dam (upstream) under SDF conditions, which is probable and would adversely effect Breakneck Dam.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observation

At the time of the field inspection, there were no signs of distress or subsidence in the dam or the spillways. Seepage was observed about 12 feet downstream of the embankment toe on the west side of the secondary spillway outfall along an undercut portion of the bank. Seepage flowed as a trickle with suspended orange silt. A small stilling basin has developed downstream from the secondary spillway outfall. Serious erosion was observed on the downstream slope along the primary spillway discharge culvert.

The spillways and discharge culverts were generally in good condition. Submerged and buried portions could not be observed nor could the inside of the discharge culverts. Considerable growth in the form of trees, brush and sparse grass was present on the embankment side slopes.

#### b. Design and Construction Data

Structural calculations and design drawings for the primary spillway are available from the NJDEP file. However, there is not sufficient data with respect to foundation soils and reinforcing steel to permit an evaluation of the design. Superficially the primary spillway appears to be stable, since it has performed satisfactorily since 1940 under various dynamic loading cycles without noticable distress.



There are no structural design calculations nor typical sections for the embankment on file. Filling of holes that have developed in the embankment above the primary discharge culvert has substantially altered the embankment.

c. Operating Records

No formal records are available. Reportedly the dam has served adequately with no significant evidence of structural instability since the 1940 repair work was completed. Eroded areas along the embankment slopes are filled and sodded on an almost annual basis.

Past experience indicates that the joint between the brick arch and the corrugated metal pipe arch culvert section downstream from the primary spillway has suffered limited differential movement and loss of soil from above the joint.

The headwall at the secondary spillway outfall is occasionally undercut slightly by the stilling basin at the embankment toe. Riprap was placed in this area pursuant to the 1971 annual inspection recommendations by T. A. Shaw, PE

d. Post Construction Changes

There is no record of changes after the 1940 repair construction. However, field inspection indicated several changes: 1) a secondary spillway and discharge culvert has been added, 2) the discharge culvert for the primary spillway and the embankment have been extended, 3) a concrete headwall has been constructed recently at the downstream end of the primary spillway discharge culvert and 4) embankment slopes have been steepened by periodic filling and repair.

e. Seismic Stability

Breakneck Dam is located in Seismic Zone 1 as is defined in "Recommended Guidelines for Safety Inspection of Dams," which is a zone of very low seismic activity. Experience indicates that dams in Seismic Zone 1 will have adequate stability under seismic loading conditions, if stable under static loading conditions. Breakneck Dam appears to be stable under static loading based on the field inspection observations.

## SECTION 7: ASSESSMENT AND RECOMMENDATIONS

### 7.1 Dam Assessment

#### a. Safety

Based on the hydraulic and hydrologic analyses described in Section 5: Hydraulic/Hydrologic and Appendix 4 the spillways are capable of accommodating about 31 percent of the PMF (62 percent of the SDF) without overtopping the dam. This flow is dependent on the intact retention capacity of Centennial Lake Dam (upstream). The hazard classification of the dam is "High". A storm of magnitude equivalent to the SDF (1/2 PMF) would overtop and probably cause the dam to fail. The breaching of Breakneck Dam would result in a maximum SDF stage in Lake Pine (downstream) about 2.1 feet above the non-breach SDF stage, and probable would not significantly increase the potential for loss of life in the downstream area. It is therefore concluded that Breakneck Dam spillways are inadequate.

Outwardly, the structural integrity of the dam appears to be adequate based on the field inspection, however sufficient data is not available to permit a complete assessment of the present structural condition of the dam and appurtenances. Reportedly, the joint between the brick arch and the corrugated metal arch has experienced differential movement and loss of soil from above, and is therefore an area of potential weakness.

#### b. Adequacy of Information

Information sources for this study include: 1) field investigations, 2) 1940 repair design calculations, construction drawings, "Application for Permit for Construction or Repair of Dam", dam inspection reports and miscellaneous correspondence

in the NJDEP file, 3) USGS quadrangles, 4) aerial photographs from Burlington County and 6) consultation with local municipal officials.

Information and data collected for Breakneck Dam is sufficient to permit a Phase I assessment of the dam with respect to spillway adequacy and outward structural stability.

c. Necessity for Additional Data/Evaluation

Additional information in the form of a comprehensive topographic survey, borings, probes and seepage pressure analyses should be obtained, together with seepage observations along the downstream toe of the dam, to permit an accurate analysis of dam stability, subsequent to the issuance of this report.

7.2 Recommendations

a. Remedial Measures

It is recommended that the following remedial measures be undertaken by the owner in the near future:

1. All trees and brush on the earthfill embankment should be cut off at ground level and removed with minimal disturbance of the embankment surface.
2. Eroded areas and bare areas should be filled and stabilized with ground cover vegetation in the near future. Positive drainage should be provided along the crest road.
3. The submerged portions of the spillway and inaccessible portions of the discharge culverts should be inspected for distress and deterioration with the lake drawn down.

Concrete surfaces in the spillways should be sand blasted and coated with an epoxy sealant after all cracks are carefully inspected and pressure grouted.

4. Debris accumulated in the outlet works and around the spillways should be removed.
5. Seepage area should be monitored periodically so that the rate and source can be determined.

b. Maintenance

The owner of the dam should initiate a formal program of annual inspection and maintenance with special attention given to the culvert joint. The inspections should be performed by a qualified professional engineer and the observations and measurements should be recorded on standardized check-list forms. Inspection check-lists and complete records of maintenance should be included in a permanent file, available for public inspection.

Repairs should be performed as required and the following maintenance should be performed annually: remove brush and trees from the embankment, fill and stabilize eroded and bare areas, clear debris from the spillway openings and the downstream channel, point deteriorated sections of the brick arch discharge culvert and seal the joint between the culvert sections.

Furthermore, the lake should be drained at least once every five years to permit a complete inspection and repair of the dam and appurtenances.

c. Additional Studies

A qualified professional engineer should be engaged in the near future to perform a comprehensive dam stability analysis



with special attention given to the area along the corrugated metal pipe arch and the culvert joint. A topographic survey, borings, test probes and seepage pressure evaluations should be performed as part of the stability analysis, and typical soil sections for the embankment should be developed along originally constructed areas, along the culverts, along areas that have undergone substantial filling since the 1940 repairs and along suspected seepage paths. Seepage and steepness of side slopes should be reviewed carefully with respect to the typical dam sections developed.

In addition, the downstream toe of the embankment should be thoroughly inspected with the downstream lake level drawn down. This area should be thoroughly investigated for seepage and animal burrows, especially in the area of the corrugated metal pipe arch outfall and the undercut bank of the natural channels.

The owner should engage a qualified professional engineer soon to perform a more sophisticated hydraulic and hydrologic analyses of the spillways, the downstream channel and the contributing watershed. Based on the findings of these analyses, the dam and spillways should be modified to accommodate a storm equivalent to the SDF without overtopping.

PLATES




PLATE I

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

# KEY MAP BREAKNECK DAM

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

I.D. N.J. 00425

SCALE: NONE

DATE: FEBRUARY, 1979




PLATE 2

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY


# INSPECTION AND EVALUATION OF DAMS VICINITY MAP BREAKNECK DAM

I.D. N.J. 00425

SCALE: AS SHOWN

DATE: FEBRUARY, 1979





#### Legend

- M-23 Unconsolidated stratified silty sand and narrowly graded sand of marine origin (Kirkwood Sands).
- AR/Z Silt and sand, with some clay and significant organic matter near the surface.

#### Note

Information taken from Rutgers University Soil Survey of New Jersey, Report No. 20 Burlington County and Geologic Map of New Jersey prepared by Lewis and Kummel.

PLATE 3

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

### SOIL MAP BREAKNECK DAM

I.D. N.J. 00425

SCALE: NONE

DATE: FEBRUARY, 1979






PLATE 4

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY


DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENV. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS  
TOPOGRAPHICAL MAP  
BREAKNECK DAM

I.D.N.J. 00425

SCALE: NONE

DATE: MARCH, 1979



**NOTE:**

Information taken from updated plan  
by Albert C. Jones prepared in or prior to 1940  
and from field inspection December 19, 1978.




PLATE 5

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

GENERAL PLAN


BREAKNECK DAM

I.D. N.J. 00425


SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979



2



PLAN




SECTION




<b>STORCH ENGINEERS</b> FLORHAM PARK, NEW JERSEY	DIVISION OF WATER RESC N.J. DEPT. OF ENVIR. PROT TRENTON, NEW JERSEY
<b>INSPECTION AND EVALUATION OF DAMS</b> <b>PRIMARY SPILLWAY</b> BREAKNECK DAM	
I.D. N.J. 00425	SCALE: NOT TO SCALE
	DATE: FEBRUARY, 1979







PLAN



SECTION



AN




TION

PLATE 7

<b>STORCH ENGINEERS</b> FLORHAM PARK, NEW JERSEY	DIVISION OF WATER RESOURCES N.J. DEPT. OF ENVIR. PROTECTION TRENTON, NEW JERSEY
<b>INSPECTION AND EVALUATION OF DAMS</b> <b>SECONDARY SPILLWAY</b> BREAKNECK DAM	
I.D.N.J. 00425	SCALE: NOT TO SCALE
DATE: FEBRUARY, 1979	

2



**NOTE:**

*Information taken From Field  
inspection December 19, 1978.*

**PLATE 8**

**STORCH ENGINEERS**  
FLORHAM PARK, NEW JERSEY

**DIVISION OF WATER RESOURCES**  
**N.J. DEPT. OF ENVIR. PROTECTION**  
TRENTON, NEW JERSEY


**INSPECTION AND EVALUATION OF DAMS**

**SECTION A-A**  
**BREAKNECK DAM**

I.D.N.J. 00425

SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979



**NOTE**

Information taken from updated plan  
by Albert C. Jones prepared in or prior to 1940  
and from field inspection December 19, 1978.




PLATE 9

STORCH ENGINEERS  
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES  
N.J. DEPT. OF ENVIR. PROTECTION  
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

## PHOTO LOCATION PLAN

BREAKNECK DAM

ID NJ 00425

SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979

2



APPENDIX 1

Check List - Visual Inspection

Check List - Engineering Data

J.G. Recorder

# CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SEE PAGE ON LEAKAGE	N.A.	
STRUCTURE TO ADJUTMENT/EMBANKMENT JUNCTIONS	N.A.	
DRAINS	N.A.	
WATER PASSAGES	N.A.	
FOUNDATION	N.A.	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	N.A.	
STRUCTURAL CRACKING	N.A.	
VERTICAL AND HORIZONTAL ALIGNMENT	N.A.	
MONOLITH JOINTS	N.A.	
CONSTRUCTION JOINTS	N.A.	

## EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None	
SLOUGHING OR EROSION OF EMBANKMENT AND ADJUTENT SLOPES	Significant erosion on downstream face of embankment adjacent to primary spill- way discharge culvert. Minor erosion along upstream and downstream faces of embankment.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Horizontal: straight with slight curve at east end. Vertical: level	
RIPRAP FAILURES	Rip Rap placed at outlet of secondary spillway discharge culvert is scoured away.	



## EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
GENERAL	Embankment sandy with sparse grass and extensive brush and tree growth.	
JUNCTION OF EMBANKMENT AND ADJUTANT, SPILLWAY AND DAM	Satisfactory except on west side of discharge culvert for primary spillway where serious erosion from poor road drainage has occurred. Joint between brick arch and corrugated metal pipe arch downstream of primary spillway not accessible.	
ANY NOTICEABLE SEEPAGE	One seepage zone at edge of downstream channel 12' from secondary spillway discharge outlet. Seepage discharge contains orange silt.	
STAFF GAGE AND RECORDER	None	
DRAINS	None observed	

# OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	See Discharge Channel for Primary Spillway..	
INTAKE STRUCTURE	Slide gate at upstream end of primary spillway- could not be clearly observed. Walkway spanning drop inlet satisfactory condition.	Operating mechanism not operated at time of inspection.
OUTLET STRUCTURE	N.A.	
OUTLET CHANNEL	See Discharge Channel for Primary Spillway.	
EMERGENCY GATE	Same as Intake Structure.	

# UNCATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Appears to be in satisfactory condition. Debris accumulated along weir and in drop inlet. Open top on drop inlet is a physical safety hazard.	Submerged by overflow. Surface of conc. has exposed aggregate. Conc. weir consists of walls of drop inlet.
APPROACH CHANNEL	N.A.	
DISCHARGE CHANNEL	Appears to be in satisfactory condition. Concrete of outlet headwall in good condition.	Arch culvert through dam. Upstream end - brick arch. Downstream end - CMP arch. The two arch components have different cross-section dimensions.
BRIDGE AND PIERS	N.A.	

# GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Generally in good condition. Surface of concrete has exposed aggregate. Concrete headwall in satisfactory condition. Debris accumulated along weir and in drop inlet. Open top on drop inlet is a physical safety hazard.	Spillway consists of uncontrolled weir combined with timber stoplog gate. Conc. weir consists of walls of drop, inlet.
APPROACH CHANNEL	N.A.	
DISCHARGE CHANNEL	Appears to be in satisfactory condition. Pipes not completely observed. Debris accumulated in pipes and in outlet.	2 - 36" diam. CMP
BRIDGE AND PIERS	N.A.	
GATES AND OPERATION EQUIPMENT	Timber stoplogs appear to be in satisfactory condition.	Submerged by overflow at time of inspection.

INSTRUMENTATION			REMARKS OR RECOMMENDATIONS
VISUAL EXAMINATION	None		
NONINVENTATION/SURVEYS			
OBSERVATION WELLS	None		
WEIRS	None		
PIEZOMETERS	None		
OTHER	N.A.		



RESERVOIR

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

SLOPES

Slope of lake shore are moderate to steep  
(3% to greater than 10%)

SEDIMENTATION

Unknown

DOWNSTREAM CHANNEL

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

CONDITION

(OBSTRUCTIONS,  
DEBRIS, ETC.)

Primary spillway discharges into  
stilling basin which flows by natural  
channel into natural channel flowing  
from secondary spillway. Streams  
generally free of significant ob-  
structions. Some debris observed.

SLOPES

Slopes of stream banks moderate.

APPROXIMATE NO.  
OF HOMES AND  
POPULATION

Lake Pine is located approx. 1000 feet  
downstream from the dam. Approx. 70  
homes along shores of Lake Pine.

**CHECK LIST**  
**ENGINEERING DATA**  
**DESIGN, CONSTRUCTION, OPERATION**

ITEM	REMARKS
PLAN OF DAM	Not Available
REGIONAL VICINITY MAP	Available
CONSTRUCTION HISTORY	Available for 1940 repair work.
TYPICAL SECTIONS OF DAM	Not Available
HYDROLOGIC/HYDRAULIC DATA	Available
OUTLETS - PLAN	Available for Primary Outlet Not Available for Secondary Outlet
- DETAILS	
- CONSTRAINTS - DISCHARGE RATINGS	
RAINFALL/RESERVOIR RECORDS	Not Available

ITEM	REMARKS
DESIGN REPORTS	Not Available
GEOLOGY REPORTS	Not Available
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	Available for 1940 repair of Primary Spillway Not Available
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Not Available
POST-CONSTRUCTION SURVEYS OF DAM	Annual Report by T.A. Shaw, P.E. Jan. 20, 1971
BORROW SOURCES.	Unknown

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	Not Available
HIGH POOL RECORDS	Not Available
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	Annual Report By T.A. Shaw, P.E., Jan. 20, 1971
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	Dam breached in early Sept. 1940. Inspection Report by John C. King on Sept. 4, 1940
MAINTENANCE OPERATION RECORDS	No formal records.



ITEM	REMARKS
------	---------

SPILLWAY PLAN

SECTIONS

Available for Primary Spillway

DETAILS

Not available for Secondary Spillway

OPERATING EQUIPMENT  
PLANS & DETAILS

Available for slide gate on Primary Spillway

APPENDIX 2

Photographs



PHOTO 1  
PRIMARY SPILLWAY



PHOTO 2  
PRIMARY SPILLWAY DISCHARGE CULVERT

19 DEC. 1978



PHOTO 3

SECONDARY SPILLWAY




PHOTO 4

SECONDARY SPILLWAY DISCHARGE PIPES

19 DEC. 1978



PHOTO 5

DOWNSTREAM FACE OF DAM



PHOTO 6

PAVED ROAD ON CREST OF DAM

19 DEC. 1978





PHOTO 7

CONCRETE STRUT ACROSS PRIMARY SPILLWAY.  
BRICK ARCH CULVERT.



PHOTO 8

EROSION AT DOWNSTREAM HEADWALL FOR PRIMARY  
SPILLWAY DISCHARGE CULVERT.



PHOTO 9

SEEPAGE AT DOWNSTREAM CHANNEL



PHOTO 10

DOWNSTREAM CHANNEL

19 DEC. 1978

APPENDIX 3

Engineering Data

CHECK LIST  
HYDROLOGIC AND HYDRAULIC DATA  
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Mostly undeveloped wooded and swampy areas with substantial residential development along lake shores.

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 51 (125 acre-ft.)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): N.A.

ELEVATION MAXIMUM DESIGN POOL: 57.4

ELEVATION TOP DAM: 55.8

PRINCIPAL SPILLWAY CREST: Concrete Box Drop Inlet

- a. Elevation 51.0
- b. Type Concrete Box Drop Inlet
- c. Width 11 inches
- d. Length 43 feet
- e. Location Spillover Inside Drop Inlet
- f. Number and Type of Gates (1) 15"x15" manual slide gate

AUXILIARY SPILLWAY CREST: Concrete Box Drop Inlet w/stoplogs

- a. Elevation 50.6 (Stoplogs), 51.2 (Sidewalls)
- b. Type Concrete Box Drop Inlet
- c. Width 3 inches (Stoplogs), 8 inches (Sidewalls)
- d. Length 2.5' (Stoplogs), 11.5' (Sidewalls)
- e. Location Spillover Inside Drop Inlet
- f. Number and Type of Gates 2.5' Stoplogs

OUTLET WORKS: Slide Gate on Primary Spillway

- a. Type Manual Gate, 15" x 15"
- b. Location South face in SW corner of Primary Spillway
- c. Entrance invert 41.6
- d. Exit invert 41.6
- e. Emergency draindown facilities: Slide Gate

HYDROMETEOROLOGICAL GAGES: None

- a. Type N.A.
- b. Location N.A.
- c. Records N.A.

MAXIMUM NON-DAMAGING DISCHARGE:

(Lake stage equal to top of dam) 1298 c.f.s.



APPENDIX 4

Hydrologic Computations

STORCH ENGINEERS

Sheet 1 of 13

Project 1132

Made By RL Date 5-7-79

Breakneck Dam (Taunton Lake)

Chkd By DRP Date 3-11-79

Size classification

Storage volume of top of dam. 354 AC-ft

Average depth of lake 6 ft.

Hydraulic height of dam 14.2 ft

Size classification Small

Hazard Potential Classification

Number of inhabitable structures 15 (estimated)

Hazard potential classification high

Recommended SDF ( $\frac{1}{2}$  PMF to PMF) use  $\frac{1}{2}$  PMF

Hydrologic Analysis

The HEC-1-DB will be used to route the flood in the subarea by Clark's method and then combined with the outflow hydrograph from Centennial Lake Dam to form the total hydrograph to Breakneck Dam.

Total drainage area = 13.0 sq. mi.  
Centennial drainage area = 7.3 sq. mi.  
Incremental Drainage Area = 5.7 sq. mi.

STORCH ENGINEERS

Sheet 2 of 13

Project 1132

Made By PL Date 3-7-79

Breakneck Dam

Chkd By Dry Date 3-11-79

### Precipitation

Re: "Design of Small Dams" USDI 1973

From fig 15, Zone 6

Probable Maximum Precipitation = 27 inches  
for 6 hr duration and 10 sq. mi area

<u>Duration (hrs)</u>	<u>% PMP</u>
6	100
12	109
24	117

### Infiltration Data

Since watershed area consists of high infiltration type soil and covered with woodlots, max. infiltration will be used.

USE initial infiltration 1.5 inches  
constant infiltration 0.15 inches

### Time of concentration & Clark's parameter

By the use of

$$T_c + R = 21 (DA/s)^{0.22} (St)^{0.33} (1.0 + 0.3 I)^{-0.28}$$

$$\frac{R}{T_c + R} = 0.76$$

ITEM

MONITORING

MODIFICATION

HIGH POOL

POST CONSTRUCTION STUDIES AND

PRIOR ACCIDENT DESCRIPTIONS AND REPORTS

MAINTENANCE OPERATION RECORDS

STORCH ENGINEERS

Sheet 3 of 13Project 1132Made By RL Date 3-7-79Breakneck DamChkd By Drf Date 3-14-79Cont. Tc & R

$$\begin{aligned}
 DA &= 5.7 \text{ sq mi} \\
 S &= 26.3 \text{ ft/mi} \\
 S_f &= 3\% \\
 I &= 3\%
 \end{aligned}$$

$$T_c = 4.36 \text{ hr.}$$

$$R = 13.64$$

Lake Storage Volume

Information from USGS &amp; Aerial Photos

StageSurface AreaEL USGS

41.6

0 Ac

51

39 Ac

60

78 Ac

(Note EL 51 USGS = EL 93.0 shown on plan)

HEC-1-DB program will develop storage capacity  
from surface area and el.

STORCH ENGINEERS





Sheet 4 of 13

Project 1132

Made By PL Date 3-7-79

Breakneck Dam

Chkd By Ekw Date 3-13-79



- SECONDARY SPILLWAY -

- PRIMARY SPILLWAY -

All dimensions shown are inside measurements



STORCH ENGINEERS

Sheet 5 of 13Project 1132Made By RL Date 4-4-79Brenkneck DamChkd By FAW Date 4-4-79Stage Discharge CalculationPrimary Spillway (Weir flow)

Effective length  $46.2 - 1.2 = 45$  ft.  
 (1.2 ft is the correction  $\approx 0.2H$  at  
 the ends of spillway and  $H$  average  $\approx 3'$   
 is used.)

(ft) W.L.	(ft) h	C	(cfs) $Q = CLH^{3/2}$
51	0	-	0
52	1	3.0	135
53	2	3.3	420
54	3	3.3	772
55	4	3.3	1188
56	5	3.3	1660
57	6	3.3	2182
58	7	3.3	2750
59	8	3.3	3360
60	9	3.3	4010
62	11	3.3	5418
64	13	3.3	6961

19 DEC. 1978

Sheet 6 of 13

PROJECT: <u>Breakneck Dam 1132</u> <u>Primary Spillway Culvert</u>		DESIGNER: <u>PL</u> CHECKED: <u>EAW</u> DATE: <u>4-4-79</u>													
HYDROLOGIC AND CHANNEL INFORMATION Culvert Size (estimated) 12'10" x 8'4" CIP Arch		SKETCH STATION: <u>Primary Spillway</u> 													
$Q_1 = \text{Max with no. overtopping} = 4.4'$ $Q_2 = \text{Max with overtopping} = 12.4'$ ( $Q_1$ = DESIGN DISCHARGE, SAY $Q_{25}$ $Q_2$ = CHECK DISCHARGE, SAY $Q_{50}$ OR $Q_{100}$ )		MEAN STREAM VELOCITY = _____ MAX. STREAM VELOCITY = _____													
CULVERT DESCRIPTION (ENTRANCE TYPE)	Q (cfs)	SIZE	HEADWATER COMPUTATION										COMMENTS		
			INLET CONT.		OUTLET CONTROL				HW = H + h <sub>0</sub> - LS <sub>0</sub>					CONTROLLING HW	OUTLET VELOCITY
			H <sub>W</sub> /D	HW	K <sub>e</sub>	H	d <sub>c</sub>	d <sub>c</sub> +D/2	TW	h <sub>0</sub>	LS <sub>0</sub>	HW			
Headwall	420	12'10" x 8'4"	0.67	5.6	0.5	0.5	5.6	6	4.4	6	-	6.5	6.5	48.1	Outlet Control
"	772	"	1.0	8.3	0.5	2.4	5.2	6.3	6.7	6.8	-	9.2	9.2	50.8	"
"	1188	"	1.5	12.5	0.5	5.7	6.5	7.9	10.4	10.0	-	15.7	15.7	57.3	"
"	1660	"	2.5	20.8	0.5	11.2	7.6	8.0	12.4	12.4	-	23.6	23.6	65.2	"
"															
"															
"															
SUMMARY & RECOMMENDATIONS:															

19 DEC. 1978

STORCH ENGINEERS

Sheet 7 of 13


Project 1132

Made By RL Date 4-4-79

Breakneck Dam

Chkd By EAW Date 4-5-79

Stage Discharge Curves  
for  
Primary Spillway weir  
and  
Primary Spillway culvert




STORCH ENGINEERS

Sheet 8 of 13Project 1132Made By RL Date 4-4-79Breakneck DamChkd By EAW Date 4-5-79Stage Discharge Calculation

Secondary Spillway (weir flow)

Effective length  $L_2 = 11.5' - 1.2' = 10.3'$   
 " "  $L_{2a} = 2.5' - 0.2' = 2.3'$



WL (ft)	$h_2$	$h_{2a}$	$C_2$	$C_{2a}$	$Q_2$	$Q_{2a}$	$\Sigma Q$ (cfs)
51	0	0.4	2.8	3.3	0	2	2
52	0.8	1.4	3.0	3.3	22	13	35
53	1.8	2.4	3.3	3.3	82	28	110
54	2.8	3.4	3.3	3.3	159	48	207
55	3.8	4.4	3.3	3.3	252	70	322
56	4.8	5.4	3.3	3.3	357	95	452
57	5.8	6.4	3.3	3.3	475	123	598
58	6.8	7.4	3.3	3.3	603	153	756
59	7.8	8.4	3.3	3.3	740	185	925
60	8.8	9.4	3.3	3.3	887	219	1106
62	10.8	11.4	3.3	3.3	1206	292	1498
64	12.8	13.4	3.3	3.3	1557	376	1933

AD-A069 907

NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/6 13/2  
NATIONAL DAM SAFETY PROGRAM. BREAKNECK DAM (NJ-00425), DELAWARE--ETC(U)  
MAY 79 R J MCDERMOTT

DACW61-78-C-0124

NL


UNCLASSIFIED

2 OF 2

AD  
A069907







MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

PROJECT: <u>Brenkneck Dam</u>		DESIGNER: <u>RL</u>	
Secondary Spillway Culvert		DATE: <u>4-4-79</u>	

HYDROLOGIC AND CHANNEL INFORMATION										SKETCH									
$Q_1 = \underline{\hspace{2cm}}$ $Q_2 = \underline{\hspace{2cm}}$ $TW_1 = \underline{\hspace{2cm}}$ $TW_2 = \underline{\hspace{2cm}}$ $(Q_1 = \text{DESIGN DISCHARGE, SAY } Q_{25}$ $Q_2 = \text{CHECK DISCHARGE, SAY } Q_{50} \text{ OR } Q_{100})$																			

CULVERT DESCRIPTION (ENTRANCE TYPE)	Q	SIZE	HEADWATER COMPUTATION										CONTROLLING HW	OUTLET VELOCITY	CONST W.L.	COMMENTS
			INLET CONT.		OUTLET CONTROL				HW = H + h <sub>0</sub> - LS <sub>0</sub>							
			HW/D	HW	K <sub>e</sub>	H	d <sub>c</sub>	d <sub>c</sub> +D/2	TW	h <sub>0</sub>	LS <sub>0</sub>	HW				
Headwall	110	24" x 24"	1.5	4.5	0.5	1.6	2.4	2.7	0	2.7	1.3	3	4.5	52.3	Inlet control	
"	207	"	X	X	0.5	5.8	3	3	3	5.0	1.3	9.5	57.3	Outlet control		
"	322	"	X	X	0.5	14.0	3	3	3	7.7	1.3	20.4	68.2	Outlet control		

SUMMARY & RECOMMENDATIONS:

RL  
 EAW  
 4-5-79  
 4-5-79  
 Sheet 9 of 13

Figure 7

STORCH ENGINEERS

Sheet 10 of 13


Project 1132

Made By RL Date 4-4-79

Breakneck Dam

Chkd By EAW Date 4-5-79

Stage Discharge Curve  
for  
Secondary Spillway weir  
and  
Secondary Spillway culverts



STORCH ENGINEERS

Sheet 11 of 13Project 1132Made By RL Date 4-4-79Breakneck DamChkd By EAW Date 4-5-77Stage Discharge TablePrimary Spillway

W.L.(ft)	Q(cfs)
51	0
52	135
53	420
54	772
55	1070
Top of dam 55.8	
56	1110
57	1190
58	1280
59	1340
60	1380
62	1490
64	1580

Secondary Spillway

W.L.(ft)	Q(cfs)
51	2
52	35
53	110
54	155
55	180
Top of dam 55.8	
56	200
57	208
58	220
59	240
60	255
62	285
64	300

STORCH ENGINEERS

Sheet 12 of 13


Project 1132

Made By RL Date 4-5-79

Breakneck Dam

Chkd By EAW Date 4-5-79

Elevation - Discharge Curve  
Breakneck Dam Spillways





STORCH ENGINEERS

Sheet 13 of 13

Project 1132

Made By RL Date 3-13-79

Breakneck Dam (Taunton Lake)

Chkd By EAW Date 3-13-79

Outlet Works Capacity

Normal pool elevation 51.0 ft.

Normal depth at outlet works 9.4 ft

Discharge occurs thru 15" x 15" slide gate

$$Q = CA \sqrt{2gh}$$

$$C = 0.6$$

$$A = 1.56 \text{ sq ft}$$

$$h = 9.4 - 0.6 = 8.8 \text{ (To center of gate)}$$

$$\begin{aligned} Q_{\max} &= 0.6 (1.56) \sqrt{2g(8.8)} \\ &= \underline{\underline{22.3 \text{ cfs}}} \end{aligned}$$

HEC-1-DB COMPUTATIONS



.....  
FLOOD HYDROGRAPH PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
.....  
LAST MODIFICATION 26 FEB 79  
.....

RJN DATE# 78/04/17  
TIME# 09.19.39.

DAM SAFETY ANALYSIS NEW JERSEY  
CENTENNIAL LAKE DAM/BREAKNECK DAM  
PMF ROUTING

NO	NHR	NMIN	IDAY	JOPER	INW	LRPT	TRACE	IPLI	IPRT	INSTAN
300	1	0	0	5	0	0	0	0	3	0

MULTI-PLAN ANALYSES TO BE PERFORMED  
NPLAN= 1 NRTIO= 1 LRTIO= 1

RTIOS= .50

.....  
SUB-AREA RUNOFF COMPUTATION  
SUBAREA INFLOW HYDROGRAPH FOR TAUNTON LAKE  
ISTAO ICOMP IECON ITAPE JPLI JPRI INAME ISTAGE IAUO  
TAUN 0 0 0 0 0 0 0 0

IMYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	0	5.70	0.00	5.70	0.00	0.000	0	0	0

PRECIP DATA  
R6 R12 R24 R48 R72 R96  
27.00 100.00 109.00 117.00 0.00 0.00 0.00

TRSPC COMPUTED BY THE PROGRAM IS .800

LRDPT	STRKR	DLTKR	RTIOL	ERAIN	STRSK	RTIOK	STIRL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.50	.15	0.00	0.00

LOSS DATA  
TC= 4.36 RE 13.54 NTA= 0  
UNIT HYDROGRAPH DATA

STRTQ= -1.00 RECESION DATA  
ORCSN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH	75 END-OF-PERIOD ORIGINATES, LAG=	4.63 HOURS, CP=	.28 VOL= 1.00
20.	75.	197.	183.
147.	137.	170.	170.
171.	127.	82.	82.
34.	118.	95.	42.
16.	110.	46.	20.
4.	53.	22.	19.
	27.	10.	4.
	13.	5.	2.
	5.	2.	2.
	3.		



MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW COMP Q	MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1	00	123	12	00	12	5	1	00	151	00	00	00	00
1	00	123	12	00	12	5	1	00	152	00	00	00	00
1	00	123	12	00	12	5	1	00	153	00	00	00	00
1	00	123	12	00	12	5	1	00	154	00	00	00	00
1	00	123	12	00	12	5	1	00	155	00	00	00	00
1	00	123	12	00	12	5	1	00	156	00	00	00	00
1	00	123	12	00	12	5	1	00	157	00	00	00	00
1	00	123	12	00	12	5	1	00	158	00	00	00	00
1	00	123	12	00	12	5	1	00	159	00	00	00	00
1	00	123	12	00	12	5	1	00	160	00	00	00	00
1	00	123	12	00	12	5	1	00	161	00	00	00	00
1	00	123	12	00	12	5	1	00	162	00	00	00	00
1	00	123	12	00	12	5	1	00	163	00	00	00	00
1	00	123	12	00	12	5	1	00	164	00	00	00	00
1	00	123	12	00	12	5	1	00	165	00	00	00	00
1	00	123	12	00	12	5	1	00	166	00	00	00	00
1	00	123	12	00	12	5	1	00	167	00	00	00	00
1	00	123	12	00	12	5	1	00	168	00	00	00	00
1	00	123	12	00	12	5	1	00	169	00	00	00	00
1	00	123	12	00	12	5	1	00	170	00	00	00	00
1	00	123	12	00	12	5	1	00	171	00	00	00	00
1	00	123	12	00	12	5	1	00	172	00	00	00	00
1	00	123	12	00	12	5	1	00	173	00	00	00	00
1	00	123	12	00	12	5	1	00	174	00	00	00	00
1	00	123	12	00	12	5	1	00	175	00	00	00	00
1	00	123	12	00	12	5	1	00	176	00	00	00	00
1	00	123	12	00	12	5	1	00	177	00	00	00	00
1	00	123	12	00	12	5	1	00	178	00	00	00	00
1	00	123	12	00	12	5	1	00	180	00	00	00	00
1	00	123	12	00	12	5	1	00	181	00	00	00	00
1	00	123	12	00	12	5	1	00	182	00	00	00	00
1	00	123	12	00	12	5	1	00	183	00	00	00	00
1	00	123	12	00	12	5	1	00	184	00	00	00	00
1	00	123	12	00	12	5	1	00	185	00	00	00	00
1	00	123	12	00	12	5	1	00	186	00	00	00	00
1	00	123	12	00	12	5	1	00	187	00	00	00	00
1	00	123	12	00	12	5	1	00	188	00	00	00	00
1	00	123	12	00	12	5	1	00	189	00	00	00	00
1	00	123	12	00	12	5	1	00	190	00	00	00	00
1	00	123	12	00	12	5	1	00	191	00	00	00	00
1	00	123	12	00	12	5	1	00	192	00	00	00	00
1	00	123	12	00	12	5	1	00	193	00	00	00	00
1	00	123	12	00	12	5	1	00	194	00	00	00	00
1	00	123	12	00	12	5	1	00	195	00	00	00	00
1	00	123	12	00	12	5	1	00	196	00	00	00	00
1	00	123	12	00	12	5	1	00	197	00	00	00	00
1	00	123	12	00	12	5	1	00	198	00	00	00	00
1	00	123	12	00	12	5	1	00	199	00	00	00	00
1	00	123	12	00	12	5	1	00	200	00	00	00	00
1	00	123	12	00	12	5	1	00	201	00	00	00	00
1	00	123	12	00	12	5	1	00	202	00	00	00	00
1	00	123	12	00	12	5	1	00	203	00	00	00	00
1	00	123	12	00	12	5	1	00	204	00	00	00	00
1	00	123	12	00	12	5	1	00	205	00	00	00	00
1	00	123	12	00	12	5	1	00	206	00	00	00	00
1	00	123	12	00	12	5	1	00	207	00	00	00	00
1	00	123	12	00	12	5	1	00	208	00	00	00	00
1	00	123	12	00	12	5	1	00	209	00	00	00	00
1	00	123	12	00	12	5	1	00	210	00	00	00	00





[illegible]

# HYDROGRAPH AT STA TAVN FOR PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	2165.	1990.	1290.	544.		39549.
CMS	61.	58.	37.	15.		1120.
INCHES		3.85	8.42	10.65		10.76
AC-FT		82.31	218.94	270.45		273.24
THOUS CU M		987.	2559.	3235.		3269.
		1217.	3157.	3931.		4032.

\*\*\*\*\*

## SUB-AREA RUNOFF COMPUTATION

### SUBAREA INFLOW HYDROGRAPH FOR CENTENNIAL LAKE

ISIAQ	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO
CENT	0	0	0	0	0	1	0	0

#### HYDROGRAPH DATA

TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
7.30	0.00	0.000	0	1	0

#### PRECIP DATA

R48	R72	R96
0.00	0.00	0.00

#### LOSS DATA

ERAIN	ERATL	RIIOK	SIRIL	CNSTL	ALSMX	RIIMP
0.00	0.00	1.00	1.55	.15	0.00	0.00

#### UNIT HYDROGRAPH DATA

TC= 8.70 RE 27.70 NTA= 0

#### RECESSION DATA

GRCSVE -0.05 RTIOE= 2.00

#### END-OF-PERIOD ORDINATES, LAG=

5.	17.	35.	53.	71.	89.	107.	125.	143.	161.	179.	197.	215.	233.	251.	269.	287.	305.	323.	341.	359.	377.	395.	413.	431.	449.	467.	485.	503.	521.	539.	557.	575.	593.	611.	629.	647.	665.	683.	701.	719.	737.	755.	773.	791.	809.	827.	845.	863.	881.	899.	917.	935.	953.	971.	989.	1007.	1025.	1043.	1061.	1079.	1097.	1115.	1133.	1151.	1169.	1187.	1205.	1223.	1241.	1259.	1277.	1295.	1313.	1331.	1349.	1367.	1385.	1403.	1421.	1439.	1457.	1475.	1493.	1511.	1529.	1547.	1565.	1583.	1601.	1619.	1637.	1655.	1673.	1691.	1709.	1727.	1745.	1763.	1781.	1799.	1817.	1835.	1853.	1871.	1889.	1907.	1925.	1943.	1961.	1979.	1997.	2015.	2033.	2051.	2069.	2087.	2105.	2123.	2141.	2159.	2177.	2195.	2213.	2231.	2249.	2267.	2285.	2303.	2321.	2339.	2357.	2375.	2393.	2411.	2429.	2447.	2465.	2483.	2501.	2519.	2537.	2555.	2573.	2591.	2609.	2627.	2645.	2663.	2681.	2699.	2717.	2735.	2753.	2771.	2789.	2807.	2825.	2843.	2861.	2879.	2897.	2915.	2933.	2951.	2969.	2987.	3005.	3023.	3041.	3059.	3077.	3095.	3113.	3131.	3149.	3167.	3185.	3203.	3221.	3239.	3257.	3275.	3293.	3311.	3329.	3347.	3365.	3383.	3401.	3419.	3437.	3455.	3473.	3491.	3509.	3527.	3545.	3563.	3581.	3599.	3617.	3635.	3653.	3671.	3689.	3707.	3725.	3743.	3761.	3779.	3797.	3815.	3833.	3851.	3869.	3887.	3905.	3923.	3941.	3959.	3977.	3995.	4013.	4031.	4049.	4067.	4085.	4103.	4121.	4139.	4157.	4175.	4193.	4211.	4229.	4247.	4265.	4283.	4301.	4319.	4337.	4355.	4373.	4391.	4409.	4427.	4445.	4463.	4481.	4499.	4517.	4535.	4553.	4571.	4589.	4607.	4625.	4643.	4661.	4679.	4697.	4715.	4733.	4751.	4769.	4787.	4805.	4823.	4841.	4859.	4877.	4895.	4913.	4931.	4949.	4967.	4985.	5003.	5021.	5039.	5057.	5075.	5093.	5111.	5129.	5147.	5165.	5183.	5201.	5219.	5237.	5255.	5273.	5291.	5309.	5327.	5345.	5363.	5381.	5399.	5417.	5435.	5453.	5471.	5489.	5507.	5525.	5543.	5561.	5579.	5597.	5615.	5633.	5651.	5669.	5687.	5705.	5723.	5741.	5759.	5777.	5795.	5813.	5831.	5849.	5867.	5885.	5903.	5921.	5939.	5957.	5975.	5993.	6011.	6029.	6047.	6065.	6083.	6101.	6119.	6137.	6155.	6173.	6191.	6209.	6227.	6245.	6263.	6281.	6299.	6317.	6335.	6353.	6371.	6389.	6407.	6425.	6443.	6461.	6479.	6497.	6515.	6533.	6551.	6569.	6587.	6605.	6623.	6641.	6659.	6677.	6695.	6713.	6731.	6749.	6767.	6785.	6803.	6821.	6839.	6857.	6875.	6893.	6911.	6929.	6947.	6965.	6983.	7001.	7019.	7037.	7055.	7073.	7091.	7109.	7127.	7145.	7163.	7181.	7199.	7217.	7235.	7253.	7271.	7289.	7307.	7325.	7343.	7361.	7379.	7397.	7415.	7433.	7451.	7469.	7487.	7505.	7523.	7541.	7559.	7577.	7595.	7613.	7631.	7649.	7667.	7685.	7703.	7721.	7739.	7757.	7775.	7793.	7811.	7829.	7847.	7865.	7883.	7901.	7919.	7937.	7955.	7973.	7991.	8009.	8027.	8045.	8063.	8081.	8099.	8117.	8135.	8153.	8171.	8189.	8207.	8225.	8243.	8261.	8279.	8297.	8315.	8333.	8351.	8369.	8387.	8405.	8423.	8441.	8459.	8477.	8495.	8513.	8531.	8549.	8567.	8585.	8603.	8621.	8639.	8657.	8675.	8693.	8711.	8729.	8747.	8765.	8783.	8801.	8819.	8837.	8855.	8873.	8891.	8909.	8927.	8945.	8963.	8981.	8999.	9017.	9035.	9053.	9071.	9089.	9107.	9125.	9143.	9161.	9179.	9197.	9215.	9233.	9251.	9269.	9287.	9305.	9323.	9341.	9359.	9377.	9395.	9413.	9431.	9449.	9467.	9485.	9503.	9521.	9539.	9557.	9575.	9593.	9611.	9629.	9647.	9665.	9683.	9701.	9719.	9737.	9755.	9773.	9791.	9809.	9827.	9845.	9863.	9881.	9899.	9917.	9935.	9953.	9971.	9989.	10007.
----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	--------

TRSPC COMPUTED BY THE PROGRAM IS .800

MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	COMP 0	PERIOD	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP 0
0	00	12	2	00	12	7	8	151	7	151	0	0	0	8
0	00	13	2	00	12	6	7	152	8	152	0	0	0	7
0	00	14	2	00	12	6	7	153	9	153	0	0	0	7
0	00	15	2	00	12	5	7	154	0	154	0	0	0	6
0	00	16	2	00	12	5	6	155	1	155	0	0	0	6
0	00	17	2	00	12	4	6	156	1	156	0	0	0	6
0	00	18	2	00	12	4	5	157	1	157	0	0	0	5
0	00	19	2	00	12	4	4	158	1	158	0	0	0	5
0	00	20	2	00	12	4	4	159	1	159	0	0	0	5
0	00	21	2	00	12	4	4	160	1	160	0	0	0	5
0	00	22	2	00	12	4	4	161	1	161	0	0	0	5
0	00	23	2	00	12	4	4	162	1	162	0	0	0	5
0	00	24	2	00	12	4	4	163	1	163	0	0	0	5
0	00	25	2	00	12	4	4	164	1	164	0	0	0	5
0	00	26	2	00	12	4	4	165	1	165	0	0	0	5
0	00	27	2	00	12	4	4	166	1	166	0	0	0	5
0	00	28	2	00	12	4	4	167	1	167	0	0	0	5
0	00	29	2	00	12	4	4	168	1	168	0	0	0	5
0	00	30	2	00	12	4	4	169	1	169	0	0	0	5
0	00	31	2	00	12	4	4	170	1	170	0	0	0	5
0	00	32	2	00	12	4	4	171	1	171	0	0	0	5
0	00	33	2	00	12	4	4	172	1	172	0	0	0	5
0	00	34	2	00	12	4	4	173	1	173	0	0	0	5
0	00	35	2	00	12	4	4	174	1	174	0	0	0	5
0	00	36	2	00	12	4	4	175	1	175	0	0	0	5
0	00	37	2	00	12	4	4	176	1	176	0	0	0	5
0	00	38	2	00	12	4	4	177	1	177	0	0	0	5
0	00	39	2	00	12	4	4	178	1	178	0	0	0	5
0	00	40	2	00	12	4	4	179	1	179	0	0	0	5
0	00	41	2	00	12	4	4	180	1	180	0	0	0	5
0	00	42	2	00	12	4	4	181	1	181	0	0	0	5
0	00	43	2	00	12	4	4	182	1	182	0	0	0	5
0	00	44	2	00	12	4	4	183	1	183	0	0	0	5
0	00	45	2	00	12	4	4	184	1	184	0	0	0	5
0	00	46	2	00	12	4	4	185	1	185	0	0	0	5
0	00	47	2	00	12	4	4	186	1	186	0	0	0	5
0	00	48	2	00	12	4	4	187	1	187	0	0	0	5
0	00	49	2	00	12	4	4	188	1	188	0	0	0	5
0	00	50	2	00	12	4	4	189	1	189	0	0	0	5
0	00	51	2	00	12	4	4	190	1	190	0	0	0	5
0	00	52	2	00	12	4	4	191	1	191	0	0	0	5
0	00	53	2	00	12	4	4	192	1	192	0	0	0	5
0	00	54	2	00	12	4	4	193	1	193	0	0	0	5
0	00	55	2	00	12	4	4	194	1	194	0	0	0	5
0	00	56	2	00	12	4	4	195	1	195	0	0	0	5
0	00	57	2	00	12	4	4	196	1	196	0	0	0	5
0	00	58	2	00	12	4	4	197	1	197	0	0	0	5
0	00	59	2	00	12	4	4	198	1	198	0	0	0	5
0	00	60	2	00	12	4	4	199	1	199	0	0	0	5
0	00	61	2	00	12	4	4	200	1	200	0	0	0	5
0	00	62	2	00	12	4	4	201	1	201	0	0	0	5
0	00	63	2	00	12	4	4	202	1	202	0	0	0	5
0	00	64	2	00	12	4	4	203	1	203	0	0	0	5
0	00	65	2	00	12	4	4	204	1	204	0	0	0	5
0	00	66	2	00	12	4	4	205	1	205	0	0	0	5
0	00	67	2	00	12	4	4	206	1	206	0	0	0	5
0	00	68	2	00	12	4	4	207	1	207	0	0	0	5
0	00	69	2	00	12	4	4	208	1	208	0	0	0	5
0	00	70	2	00	12	4	4	209	1	209	0	0	0	5
0	00	71	2	00	12	4	4	210	1	210	0	0	0	5
0	00	72	2	00	12	4	4	211	1	211	0	0	0	5
0	00	73	2	00	12	4	4	212	1	212	0	0	0	5
0	00	74	2	00	12	4	4	213	1	213	0	0	0	5
0	00	75	2	00	12	4	4	214	1	214	0	0	0	5
0	00	76	2	00	12	4	4	215	1	215	0	0	0	5
0	00	77	2	00	12	4	4	216	1	216	0	0	0	5
0	00	78	2	00	12	4	4	217	1	217	0	0	0	5
0	00	79	2	00	12	4	4	218	1	218	0	0	0	5
0	00	80	2	00	12	4	4	219	1	219	0	0	0	5
0	00	81	2	00	12	4	4	220	1	220	0	0	0	5
0	00	82	2	00	12	4	4	221	1	221	0	0	0	5
0	00	83	2	00	12	4	4	222	1	222	0	0	0	5
0	00	84	2	00	12	4	4	223	1	223	0	0	0	5
0	00	85	2	00	12	4	4	224	1	224	0	0	0	5
0	00	86	2	00	12	4	4	225	1	225	0	0	0	5
0	00	87	2	00	12	4	4	226	1	226	0	0	0	5
0	00	88	2	00	12	4	4	227	1	227	0	0	0	5
0	00	89	2	00	12	4	4	228	1	228	0	0	0	5
0	00	90	2	00	12	4	4	229	1	229	0	0	0	5
0	00	91	2	00	12	4	4	230	1	230	0	0	0	5
0	00	92	2	00	12	4	4	231	1	231	0	0	0	5
0	00	93	2	00	12	4	4	232	1	232	0	0	0	5
0	00	94	2	00	12	4	4	233	1	233	0	0	0	5
0	00	95	2	00	12	4	4	234	1	234	0	0	0	5
0	00	96	2	00	12	4	4	235	1	235	0	0	0	5
0	00	97	2	00	12	4	4	236	1	236	0	0	0	5
0	00	98	2	00	12	4	4	237	1	237	0	0	0	5
0	00	99	2	00	12	4	4	238	1	238	0	0	0	5
0	00	100	2	00	12	4	4	239	1	239	0	0	0	5
0	00	101	2	00	12	4	4	240	1	240	0	0	0	5
0	00	102	2	00	12	4	4	241	1	241	0	0	0	5
0	00	103	2	00	12	4	4	242	1	242	0	0	0	5
0	00	104	2	00	12	4	4	243	1	243	0	0	0	5
0	00	105	2	00	12	4	4	244	1	244	0	0	0	5
0	00	106	2	00	12	4	4	245	1	245	0	0	0	5
0	00	107	2	00	12	4	4	246	1	246	0	0	0	5
0	00	108	2	00	12	4	4	247	1	247	0	0	0	5
0	00	109	2	00	12	4	4	248	1	248	0	0	0	5
0	00	110	2	00	12	4	4	249	1	249	0	0	0	5
0	00	111	2	00	12	4	4	250	1	250	0	0	0	5
0	00	112	2	00	12	4	4	251	1	251	0	0	0	5
0	00	113	2	00	12	4	4	252	1	252	0	0	0	5
0	00	114	2	00	12	4	4	253	1	253	0	0	0	5
0	00	115	2	00	12	4	4	254	1	254	0	0	0	5
0	00	116	2	00	12	4	4	255	1	255	0	0	0	5
0	00	117	2	00	12	4	4	256	1	256	0	0	0	5
0	00	118	2	00	12	4	4	257	1	257	0	0	0	5
0	00	119	2	00	12	4	4	258	1	258	0	0	0	5
0	00	120	2	00	12	4	4	259	1	259	0	0	0	5
0	00	121	2	00	12	4	4	260	1	260	0	0	0	5
0	00	122	2	00	12	4	4	261	1	261	0	0	0	5
0	00	123	2	00	12	4	4	262	1	262	0	0	0	5
0	00	124	2	00	12	4	4	263	1	263	0	0	0	5
0	00	125	2	00	12	4	4	264	1	264	0	0	0	5
0	00	126	2	00	12	4	4	265	1	265	0	0	0	5
0	00	127	2	00	12	4	4	266	1	266	0	0	0	5
0	00	128	2	00	12	4	4	267	1	267	0	0	0	5
0	00	129	2	00	12	4	4	268	1	268	0	0	0	5
0	00	130	2	00	12	4	4	269	1	269	0	0	0	5
0	00	131	2	00	12	4	4	270	1	270	0	0	0	









# ROUTED DISCHARGE THROUGH CENTENNIAL LAKE DAM

ISTAO	ICOMP	IECON	ITAPE	JPLI	JPRI	INAME	ISTAGE	IAUTO
TAUN	1	0	0	0	0	I	0	0
ROUTING DATA								
AVG	IRIS	ISAME	IOPI	IPMP	LSTR			
0.00	1	1	0	0	0			
NSTPS	INSTOL	LAG	AMSKK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	-60.	-1	
STAGE	59.60	60.50	61.00	61.50	62.00	62.50	63.00	64.00
	64.50	65.50	66.00	67.00	68.00	69.00	70.00	
FLOW	0.00	30.00	58.00	93.00	132.00	176.00	202.00	241.00
	256.00	307.00	428.00	451.00	475.00	496.00	517.00	

CAPACITY= 0. 334. 358. 1244.

ELEVATION= 48. 60. 60. 70.

COOL	CAREA	EXPL
0.0	0.0	0.0

DAM DATA  
TOPEL 66.0  
COOD 2.6  
EXPD 1.5  
DAMJID 300.

STATION TAUN, PLAN 1, RATIO 1

## END-OF-PERIOD HYDROGRAPH ORIGINATES

MO. DA	HR. MN	PERIOD	HOURS	INFLOW	OUTFLOW	STORAGE	STAGE
1.01	1.00	1	1.00	3.00	0.00	334.0	59.6
1.01	2.00	2	2.00	3.00	0.00	334.0	59.6
1.01	3.00	3	3.00	3.00	0.00	334.0	59.6
1.01	4.00	4	4.00	3.00	0.00	334.0	59.6
1.01	5.00	5	5.00	3.00	0.00	334.0	59.6
1.01	6.00	6	6.00	3.00	0.00	334.0	59.6
1.01	7.00	7	7.00	3.00	0.00	334.0	59.6
1.01	8.00	8	8.00	3.00	0.00	334.0	59.6
1.01	9.00	9	9.00	3.00	0.00	334.0	59.6
1.01	10.00	10	10.00	3.00	0.00	334.0	59.6
1.01	11.00	11	11.00	3.00	0.00	334.0	59.6
1.01	12.00	12	12.00	3.00	0.00	334.0	59.6
1.01	13.00	13	13.00	3.00	0.00	334.0	59.6
1.01	14.00	14	14.00	3.00	0.00	334.0	59.6
1.01	15.00	15	15.00	3.00	0.00	334.0	59.6
1.01	16.00	16	16.00	3.00	0.00	334.0	59.6
1.01	17.00	17	17.00	3.00	0.00	334.0	59.6
1.01	18.00	18	18.00	3.00	0.00	334.0	59.6
1.01	19.00	19	19.00	3.00	0.00	334.0	59.6
1.01	20.00	20	20.00	3.00	0.00	334.0	59.6
1.01	21.00	21	21.00	3.00	0.00	334.0	59.6
1.01	22.00	22	22.00	3.00	0.00	334.0	59.6
1.01	23.00	23	23.00	3.00	0.00	334.0	59.6
1.01	24.00	24	24.00	3.00	0.00	334.0	59.6
1.01	25.00	25	25.00	3.00	0.00	334.0	59.6
1.01	26.00	26	26.00	3.00	0.00	334.0	59.6
1.01	27.00	27	27.00	3.00	0.00	334.0	59.6
1.01	28.00	28	28.00	3.00	0.00	334.0	59.6
1.01	29.00	29	29.00	3.00	0.00	334.0	59.6
1.01	30.00	30	30.00	3.00	0.00	334.0	59.6
1.01	31.00	31	31.00	3.00	0.00	334.0	59.6
1.01	32.00	32	32.00	3.00	0.00	334.0	59.6
1.01	33.00	33	33.00	3.00	0.00	334.0	59.6
1.01	34.00	34	34.00	3.00	0.00	334.0	59.6
1.01	35.00	35	35.00	3.00	0.00	334.0	59.6
1.01	36.00	36	36.00	3.00	0.00	334.0	59.6
1.01	37.00	37	37.00	3.00	0.00	334.0	59.6
1.01	38.00	38	38.00	3.00	0.00	334.0	59.6
1.01	39.00	39	39.00	3.00	0.00	334.0	59.6
1.01	40.00	40	40.00	3.00	0.00	334.0	59.6
1.01	41.00	41	41.00	3.00	0.00	334.0	59.6
1.01	42.00	42	42.00	3.00	0.00	334.0	59.6
1.01	43.00	43	43.00	3.00	0.00	334.0	59.6
1.01	44.00	44	44.00	3.00	0.00	334.0	59.6
1.01	45.00	45	45.00	3.00	0.00	334.0	59.6
1.01	46.00	46	46.00	3.00	0.00	334.0	59.6
1.01	47.00	47	47.00	3.00	0.00	334.0	59.6
1.01	48.00	48	48.00	3.00	0.00	334.0	59.6
1.01	49.00	49	49.00	3.00	0.00	334.0	59.6
1.01	50.00	50	50.00	3.00	0.00	334.0	59.6
1.01	51.00	51	51.00	3.00	0.00	334.0	59.6
1.01	52.00	52	52.00	3.00	0.00	334.0	59.6
1.01	53.00	53	53.00	3.00	0.00	334.0	59.6
1.01	54.00	54	54.00	3.00	0.00	334.0	59.6
1.01	55.00	55	55.00	3.00	0.00	334.0	59.6
1.01	56.00	56	56.00	3.00	0.00	334.0	59.6
1.01	57.00	57	57.00	3.00	0.00	334.0	59.6
1.01	58.00	58	58.00	3.00	0.00	334.0	59.6
1.01	59.00	59	59.00	3.00	0.00	334.0	59.6
1.01	60.00	60	60.00	3.00	0.00	334.0	59.6
1.01	61.00	61	61.00	3.00	0.00	334.0	59.6
1.01	62.00	62	62.00	3.00	0.00	334.0	59.6
1.01	63.00	63	63.00	3.00	0.00	334.0	59.6
1.01	64.00	64	64.00	3.00	0.00	334.0	59.6
1.01	65.00	65	65.00	3.00	0.00	334.0	59.6
1.01	66.00	66	66.00	3.00	0.00	334.0	59.6
1.01	67.00	67	67.00	3.00	0.00	334.0	59.6
1.01	68.00	68	68.00	3.00	0.00	334.0	59.6
1.01	69.00	69	69.00	3.00	0.00	334.0	59.6
1.01	70.00	70	70.00	3.00	0.00	334.0	59.6
1.01	71.00	71	71.00	3.00	0.00	334.0	59.6
1.01	72.00	72	72.00	3.00	0.00	334.0	59.6
1.01	73.00	73	73.00	3.00	0.00	334.0	59.6
1.01	74.00	74	74.00	3.00	0.00	334.0	59.6
1.01	75.00	75	75.00	3.00	0.00	334.0	59.6
1.01	76.00	76	76.00	3.00	0.00	334.0	59.6
1.01	77.00	77	77.00	3.00	0.00	334.0	59.6
1.01	78.00	78	78.00	3.00	0.00	334.0	59.6
1.01	79.00	79	79.00	3.00	0.00	334.0	59.6
1.01	80.00	80	80.00	3.00	0.00	334.0	59.6
1.01	81.00	81	81.00	3.00	0.00	334.0	59.6
1.01	82.00	82	82.00	3.00	0.00	334.0	59.6
1.01	83.00	83	83.00	3.00	0.00	334.0	59.6
1.01	84.00	84	84.00	3.00	0.00	334.0	59.6
1.01	85.00	85	85.00	3.00	0.00	334.0	59.6
1.01	86.00	86	86.00	3.00	0.00	334.0	59.6
1.01	87.00	87	87.00	3.00	0.00	334.0	59.6
1.01	88.00	88	88.00	3.00	0.00	334.0	59.6
1.01	89.00	89	89.00	3.00	0.00	334.0	59.6
1.01	90.00	90	90.00	3.00	0.00	334.0	59.6
1.01	91.00	91	91.00	3.00	0.00	334.0	59.6
1.01	92.00	92	92.00	3.00	0.00	334.0	59.6
1.01	93.00	93	93.00	3.00	0.00	334.0	59.6
1.01	94.00	94	94.00	3.00	0.00	334.0	59.6
1.01	95.00	95	95.00	3.00	0.00	334.0	59.6
1.01	96.00	96	96.00	3.00	0.00	334.0	59.6
1.01	97.00	97	97.00	3.00	0.00	334.0	59.6
1.01	98.00	98	98.00	3.00	0.00	334.0	59.6
1.01	99.00	99	99.00	3.00	0.00	334.0	59.6
1.01	100.00	100	100.00	3.00	0.00	334.0	59.6

[illegible]

[illegible]







PEAK OUTFLOW IS 1367. AT TIME 27.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	1367.	1393.	1082.	535.	4358	140.55
INCHES	39.	37.	22.	17.5	100.	10.07
ACCU-M		1.46	5.02	8.25	24.9	10.66
THOUS		4.64	13.02	27.81	45.43	
		797.		4294.		

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

# COMBINE HYDROGRAPHS

## COMBINE HYDROGRAPHS IN TAUNTON LAKE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
TAUN	2	0	0	0	0	1	0	0

## SUM OF 2 HYDROGRAPHS AT TAUN PLAN 1 RTIO 1

	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
PEAK	2611.	2100.	1107.		89245.
CFS	74.	59.	31.		2327.
CMH	1.87	6.01	9.51		10.64
INCHES	47.46	152.70	241.53		270.34
MM	1295.	4166.	6590.		7375.
AC-FT	1597.	5139.	8128.		9397.
THOUS CU M					

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

# HYDROGRAPH ROUTING

## ROUTE HYDROGRAPH THROUGH BREAKNECK DAM

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
BRVK	1	0	0	0	0	1	0	0

ROUTING DATA	ICPT	IIMP	LSTR
AVG	0	0	0
CLOSS	0.00	0.00	0.00
0.00	0.00	0.00	0.00

NSIPS	NSTOL	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-51.	-1

STAGE	51.00	52.00	53.00	54.00	55.00	56.00	57.00	58.00	59.00	60.00
	62.00	64.00								

FLOW	1775.00	170.00	530.00	927.00	1250.00	1310.00	1398.00	1500.00	1580.00	1635.00
		1880.00								

SURFACE AREA= 0. 39. 78.

CAPACITY= 0. 122. 639.

ELEVATION= 42. 51. 60.

CREL	SPWID	COOW	EXPW	ELEVL	COOL	CAREA	EXPL
51.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

TOPEL COOD EXPD DAMJID


[illegible]

[illegible]









PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
2772.	2500.	2037.	1104.	89323.	89323.
78.	174.	58.	31.	2529.	2529.
	1.25	5.89	9.48	10.55	10.55
	47.25	149.54	240.78	7382.	7382.
	1289.	4080.	6559.	9106.	9106.
	1590.	5032.	813.		

PEAK OUTFLOW IS 2772. AT TIME 27.00 HOURS

CFS  
INCHES  
AC-FT  
THOUS. CU. M
















PEAK OUTFLOW IS	2750.	AT TIME	28.00 HOURS
PEAK	2750.		
6-HOUR	2584.		
24-HOUR	2048.		
72-HOUR	1102.		
TOTAL	8433.		
VOLUME	8433.		
INCHES	1.00		
AC-FT	1.00		
THOUS CU M	1.00		

## SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 51.00 122. 1298.	SPILLWAY CREST 51.00 122. 1298.	TOP OF DAM 53.80 134. 1298.	RATIO OF PMF	MAXIMUM RESERVOIR W.W. S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE ACQ.	MAXIMUM FLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURES HOURS
					.50	57.38	1.58	451.	2772.	25.00	27.00	0.00

# LAKE PINE DAM

## SUMMARY OF DAM SAFETY ANALYSIS

PLAN I .....

ELEVATION  
STORAGE  
OUTFLOW

INITIAL VALUE  
41.00  
45.  
0.

SPILLWAY CREST  
41.00  
45.  
0.

TOP OF DAM  
46.90  
193.  
1544.

RATIO  
OF  
PMF  
MAXIMUM  
RESERVOIR  
W.S. ELEV

.50 48.84

MAXIMUM  
DEPTH  
OVER DAM

1.94

MAXIMUM  
STORAGE  
AC-FT

267.

MAXIMUM  
OUTFLOW  
CFS

2750.

DURATION  
OVER TOP  
HOURS

19.00

TIME OF  
MAX OUTFLOW  
HOURS

28.00

TIME OF  
FAILURE  
HOURS

0.00

DAM SAFETY ANALYSIS NEW JERSEY  
CENTENNIAL LAKE DAM/BREAKNECK DAM  
PHF ROUTING

	1	0	0	0	3
A1	300	1	0	0	3
A2	31	1	1		
A3	0.50				
J1	0	TAUN			
K1	0	0	0	0	1
M1	0	27	5.7	0	
T	4.36	13.64	109	1.5	0.15
V	-1.0	-0.05	0		
X	0	0	0		
K1	0	0	0	0	1
P	0	27	7.3	0	
V	8.7	27.7	109	1.5	0.15
X	-1.0	-0.05	0		
K1	0	0	0	0	1
Y1	59.6	60.0	61.0	-59.6	63.5
Y4	64.5	65.0	66.0	62.0	64.0
Y5	256	270	307	67.0	70.0
Y6	47.9	334	428	132	202
Y7	59.6	358	1294	475	496
Y8	59.6	60	70		517
Y9	62	2.63	300		
K1	1	TAUN	0	0	1
K1	1	BKNK	0	0	1
K1	1	ROUTE	0	0	1
Y1	51	52	54	-51.0	58
Y4	62	64	55	57	59
Y5	1775	170	927	1398	1580
Y6	1880	530	1250	1310	1635
Y7	39	78			
Y8	41.6	51			
Y9	51.0				
Y10	55.8				
Y11	2.63	1.5	255	55.8	
Y12	2.0	46.0	51.0	55.8	
Y13	1	ROUTE	0	0	1
K1	1	ROUTE	0	0	1
Y1	41.0	42.0	44.0	-41.0	54.0
Y4	93	305	644	46.0	46.9
Y5	0	17	46	1448	1544
Y6	33.1	41	50	1697	2094
Y7	41.0				
Y8	46.9	2.63	1.5		
Y9	46.9				
Y10					
Y11					
Y12					
Y13					
Y14					
Y15					
Y16					
Y17					
Y18					
Y19					
Y20					
Y21					
Y22					
Y23					
Y24					
Y25					
Y26					
Y27					
Y28					
Y29					
Y30					
Y31					
Y32					
Y33					
Y34					
Y35					
Y36					
Y37					
Y38					
Y39					
Y40					
Y41					
Y42					
Y43					
Y44					
Y45					
Y46					
Y47					
Y48					
Y49					
Y50					
Y51					
Y52					
Y53					
Y54					
Y55					
Y56					
Y57					
Y58					
Y59					
Y60					
Y61					
Y62					
Y63					
Y64					
Y65					
Y66					
Y67					
Y68					
Y69					
Y70					
Y71					
Y72					
Y73					
Y74					
Y75					
Y76					
Y77					
Y78					
Y79					
Y80					
Y81					
Y82					
Y83					
Y84					
Y85					
Y86					
Y87					
Y88					
Y89					
Y90					
Y91					
Y92					
Y93					
Y94					
Y95					
Y96					
Y97					
Y98					
Y99					
Y100					



268.01  
4107.  
5066.

1  
 2  
 3  
 4  
 5  
 6  
 7  
 8  
 9  
 10  
 11  
 12  
 13  
 14  
 15  
 16  
 17  
 18  
 19  
 20  
 21  
 22  
 23  
 24  
 25  
 26  
 27  
 28  
 29  
 30  
 31  
 32  
 33  
 34  
 35  
 36  
 37  
 38  
 39  
 40  
 41  
 42  
 43  
 44  
 45  
 46  
 47  
 48  
 49  
 50  
 51  
 52  
 53  
 54  
 55  
 56  
 57  
 58  
 59  
 60  
 61  
 62  
 63  
 64  
 65  
 66  
 67  
 68  
 69  
 70  
 71  
 72  
 73  
 74  
 75  
 76  
 77  
 78  
 79  
 80  
 81  
 82  
 83  
 84  
 85  
 86  
 87  
 88  
 89  
 90  
 91  
 92  
 93  
 94  
 95  
 96  
 97  
 98  
 99  
 100  
 101  
 102  
 103  
 104  
 105  
 106  
 107  
 108  
 109  
 110  
 111  
 112  
 113  
 114  
 115  
 116  
 117  
 118  
 119  
 120  
 121  
 122  
 123  
 124  
 125  
 126  
 127  
 128  
 129  
 130  
 131  
 132  
 133  
 134  
 135  
 136  
 137  
 138  
 139  
 140  
 141  
 142  
 143  
 144  
 145  
 146  
 147  
 148  
 149  
 150  
 151  
 152  
 153  
 154  
 155  
 156  
 157  
 158  
 159  
 160  
 161  
 162  
 163  
 164  
 165  
 166  
 167  
 168  
 169  
 170  
 171  
 172  
 173  
 174  
 175  
 176  
 177  
 178  
 179  
 180  
 181  
 182  
 183  
 184  
 185  
 186  
 187  
 188  
 189  
 190  
 191  
 192  
 193  
 194  
 195  
 196  
 197  
 198  
 199  
 200  
 201  
 202  
 203  
 204  
 205  
 206  
 207  
 208  
 209  
 210  
 211  
 212  
 213  
 214  
 215  
 216  
 217  
 218  
 219  
 220  
 221  
 222  
 223  
 224  
 225  
 226  
 227  
 228  
 229  
 230  
 231  
 232  
 233  
 234  
 235  
 236  
 237  
 238  
 239  
 240  
 241  
 242  
 243  
 244  
 245  
 246  
 247  
 248  
 249  
 250  
 251  
 252  
 253  
 254  
 255  
 256  
 257  
 258  
 259  
 260  
 261  
 262  
 263  
 264  
 265  
 266  
 267  
 268  
 269  
 270  
 271  
 272  
 273  
 274  
 275  
 276  
 277  
 278  
 279  
 280  
 281  
 282  
 283  
 284  
 285  
 286  
 287  
 288  
 289  
 290  
 291  
 292  
 293  
 294  
 295  
 296  
 297  
 298  
 299  
 300  
 301  
 302  
 303  
 304  
 305  
 306  
 307  
 308  
 309  
 310  
 311  
 312  
 313  
 314  
 315  
 316  
 317  
 318  
 319  
 320  
 321  
 322  
 323  
 324  
 325  
 326  
 327  
 328  
 329  
 330  
 331  
 332  
 333  
 334  
 335  
 336  
 337  
 338  
 339  
 340  
 341  
 342  
 343  
 344  
 345  
 346  
 347  
 348  
 349  
 350  
 351  
 352  
 353  
 354  
 355  
 356  
 357  
 358  
 359  
 360  
 361  
 362  
 363  
 364  
 365  
 366  
 367  
 368  
 369  
 370  
 371  
 372  
 373  
 374  
 375  
 376  
 377  
 378  
 379  
 380  
 381  
 382  
 383  
 384  
 385  
 386  
 387  
 388  
 389  
 390  
 391  
 392  
 393  
 394  
 395  
 396  
 397  
 398  
 399  
 400  
 401  
 402  
 403  
 404  
 405  
 406  
 407  
 408  
 409  
 410  
 411  
 412  
 413  
 414  
 415  
 416  
 417  
 418  
 419  
 420  
 421  
 422  
 423  
 424  
 425  
 426  
 427  
 428  
 429  
 430  
 431  
 432  
 433  
 434  
 435  
 436  
 437  
 438  
 439  
 440  
 441  
 442  
 443  
 444  
 445  
 446  
 447  
 448  
 449  
 450  
 451  
 452  
 453  
 454  
 455  
 456  
 457  
 458  
 459  
 460  
 461  
 462  
 463  
 464  
 465  
 466  
 467  
 468  
 469  
 470  
 471  
 472  
 473  
 474  
 475  
 476  
 477  
 478  
 479  
 480  
 481  
 482  
 483  
 484  
 485  
 486  
 487  
 488  
 489  
 490  
 491  
 492  
 493  
 494  
 495  
 496  
 497  
 498  
 499  
 500  
 501  
 502  
 503  
 504  
 505  
 506  
 507  
 508  
 509  
 510  
 511  
 512  
 513  
 514  
 515  
 516  
 517  
 518  
 519  
 520  
 521  
 522  
 523  
 524  
 525

—

Σ 0

AN 1 RTIO 1

-HOUR	TOTAL	VOLUME
1107.	89243.	
31.	2527.	64
9.51	10.64	
41.53	270.34	
6590.	7375.	
8128.	9097.	

• • • • •

Σ 0  
I AUTO 0

PT 0 IPMP 0 LSTR 0

X	TSK	STORA	ISPRAT
00	0-000	-512	-1

56.00	57.00	58.00	59.00	60.00
-------	-------	-------	-------	-------

1310.00	1398.00	1500.00	1580.00	1635.00
---------	---------	---------	---------	---------

1000000 39. 78.

122. 639.

51. 60.

COOL	0.0	CARFA	0.0	EXPL	0.0
------	-----	-------	-----	------	-----

PD 5 DAMWID 255

TA  
IL  
00

STATION BKNK, PLAN 1, RATIO 1

MO. DA	HR. MN	END-OF-PERIOD HOURS	HYDROGRAPH INFLOW	ORDINATES OUTFLOW	STORAGE	STAGE
11	00	1	0	2	122	00
11	00	2	0	2	122	00
11	00	3	0	2	122	00
11	00	4	0	2	122	00
11	00	5	0	2	122	00
11	00	6	0	2	122	00
11	00	7	0	2	122	00
11	00	8	0	2	122	00
11	00	9	0	2	122	00
11	00	10	0	2	122	00
11	00	11	0	2	122	00
11	00	12	0	2	122	00
11	00	13	0	2	122	00
11	00	14	0	2	122	00
11	00	15	0	2	122	00
11	00	16	0	2	122	00
11	00	17	0	2	122	00
11	00	18	0	2	122	00
11	00	19	0	2	122	00
11	00	20	0	2	122	00
11	00	21	0	2	122	00
11	00	22	0	2	122	00
11	00	23	0	2	122	00
11	00	24	0	2	122	00
11	00	25	0	2	122	00
11	00	26	0	2	122	00
11	00	27	0	2	122	00
11	00	28	0	2	122	00
11	00	29	0	2	122	00
11	00	30	0	2	122	00
11	00	31	0	2	122	00
11	00	32	0	2	122	00
11	00	33	0	2	122	00
11	00	34	0	2	122	00
11	00	35	0	2	122	00
11	00	36	0	2	122	00
11	00	37	0	2	122	00
11	00	38	0	2	122	00
11	00	39	0	2	122	00
11	00	40	0	2	122	00
11	00	41	0	2	122	00
11	00	42	0	2	122	00
11	00	43	0	2	122	00
11	00	44	0	2	122	00
11	00	45	0	2	122	00
11	00	46	0	2	122	00
11	00	47	0	2	122	00
11	00	48	0	2	122	00
11	00	49	0	2	122	00
11	00	50	0	2	122	00
11	00	51	0	2	122	00
11	00	52	0	2	122	00
11	00	53	0	2	122	00
11	00	54	0	2	122	00
11	00	55	0	2	122	00
11	00	56	0	2	122	00
11	00	57	0	2	122	00
11	00	58	0	2	122	00
11	00	59	0	2	122	00
11	00	60	0	2	122	00
11	00	61	0	2	122	00
11	00	62	0	2	122	00
11	00	63	0	2	122	00
11	00	64	0	2	122	00
11	00	65	0	2	122	00
11	00	66	0	2	122	00
11	00	67	0	2	122	00
11	00	68	0	2	122	00
11	00	69	0	2	122	00
11	00	70	0	2	122	00
11	00	71	0	2	122	00
11	00	72	0	2	122	00
11	00	73	0	2	122	00
11	00	74	0	2	122	00
11	00	75	0	2	122	00
11	00	76	0	2	122	00
11	00	77	0	2	122	00
11	00	78	0	2	122	00
11	00	79	0	2	122	00
11	00	80	0	2	122	00
11	00	81	0	2	122	00
11	00	82	0	2	122	00
11	00	83	0	2	122	00
11	00	84	0	2	122	00
11	00	85	0	2	122	00
11	00	86	0	2	122	00
11	00	87	0	2	122	00
11	00	88	0	2	122	00
11	00	89	0	2	122	00
11	00	90	0	2	122	00
11	00	91	0	2	122	00
11	00	92	0	2	122	00
11	00	93	0	2	122	00
11	00	94	0	2	122	00
11	00	95	0	2	122	00
11	00	96	0	2	122	00
11	00	97	0	2	122	00
11	00	98	0	2	122	00
11	00	99	0	2	122	00
11	00	100	0	2	122	00

BEGIN DAN FAILURE AT 20.00 HOURS



(21)







PEAK OUTFLOW IS 5717. AT TIME 21.00 HOURS

THOUS CUM AC-F-T

THE DAM BREACH HYDROGRAPH WAS DEVELOPED USING A TIME INTERVAL OF .020 HOURS DURING BREACH FORMATION. DOWNSTREAM CALCULATIONS WILL USE A TIME INTERVAL OF 1.000 HOURS. THIS TABLE COMPARES THE HYDROGRAPH FOR DOWNSTREAM CALCULATIONS WITH THE COMPUTED BREACH HYDROGRAPH. INTERMEDIATE FLOWS ARE INTERPOLATED FROM END-OF-PERIOD VALUES.

TIME (HOURS)	TIME FROM BEGINNING OF BREACH (HOURS)	INTERPOLATED BREACH HYDROGRAPH (CFS)	COMPUTED BREACH HYDROGRAPH (CFS)	ERROR (CFS)	ACCUMULATED ERROR (CFS)	ACCUMULATED ERROR (AC-FT)
0.000	0.000	1612.	1612.	0.	0.	0.000
0.020	0.020	1694.	1665.	29.	29.	0.000
0.040	0.040	1776.	1734.	52.	81.	0.000
0.060	0.060	1858.	1787.	71.	152.	0.000
0.080	0.080	1940.	1854.	86.	238.	0.000
0.100	0.100	2022.	1925.	97.	335.	0.000
0.120	0.120	2104.	1998.	106.	443.	0.000
0.140	0.140	2187.	2074.	113.	556.	0.000
0.160	0.160	2269.	2151.	118.	673.	0.000
0.180	0.180	2351.	2231.	120.	793.	0.000
0.200	0.200	2433.	2311.	122.	915.	0.000
0.220	0.220	2515.	2397.	118.	1037.	0.000
0.240	0.240	2597.	2476.	121.	1159.	0.000
0.260	0.260	2679.	2559.	120.	1279.	0.000
0.280	0.280	2761.	2643.	122.	1397.	0.000
0.300	0.300	2843.	2727.	116.	1514.	0.000
0.320	0.320	2926.	2812.	114.	1627.	0.000
0.340	0.340	3008.	2897.	111.	1738.	0.000
0.360	0.360	3090.	2982.	108.	1846.	0.000
0.380	0.380	3172.	3067.	105.	1953.	0.000
0.400	0.400	3254.	3152.	102.	2058.	0.000
0.420	0.420	3336.	3237.	99.	2161.	0.000
0.440	0.440	3418.	3322.	96.	2263.	0.000
0.460	0.460	3500.	3407.	93.	2364.	0.000
0.480	0.480	3582.	3492.	90.	2465.	0.000
0.500	0.500	3665.	3577.	88.	2566.	0.000
0.520	0.520	3747.	3663.	84.	2667.	0.000
0.540	0.540	3829.	3748.	81.	2768.	0.000
0.560	0.560	3911.	3833.	76.	2869.	0.000
0.580	0.580	3993.	3918.	69.	2970.	0.000
0.600	0.600	4075.	4003.	61.	3072.	0.000
0.620	0.620	4157.	4088.	50.	3173.	0.000
0.640	0.640	4239.	4173.	34.	3274.	0.000
0.660	0.660	4322.	4258.	11.	3375.	0.000
0.680	0.680	4404.	4343.	-13.	3476.	0.000
0.700	0.700	4486.	4428.	-42.	3577.	0.000
0.720	0.720	4568.	4513.	-45.	3678.	0.000
0.740	0.740	4650.	4598.	-48.	3779.	0.000
0.760	0.760	4732.	4683.	-51.	3880.	0.000
0.780	0.780	4814.	4768.	-54.	3981.	0.000
0.800	0.800	4896.	4853.	-57.	4082.	0.000
0.820	0.820	4978.	4938.	-60.	4183.	0.000
0.840	0.840	5061.	5023.	-62.	4284.	0.000
0.860	0.860	5143.	5108.	-65.	4385.	0.000
0.880	0.880	5225.	5193.	-68.	4486.	0.000
0.900	0.900	5307.	5278.	-71.	4587.	0.000
0.920	0.920	5389.	5363.	-74.	4688.	0.000
0.940	0.940	5471.	5448.	-77.	4789.	0.000
0.960	0.960	5553.	5533.	-80.	4890.	0.000
0.980	0.980	5635.	5618.	-83.	4991.	0.000
1.000	1.000	5717.	5703.	-84.	5092.	0.000


•OVF•

STATION 3KNK

TIME  
(HRS)

(O) INTERPOLATED BREACH HYDROGRAPH  
(R) COMPUTED BREACH HYDROGRAPH

(••) POINTS AT NORMAL TIME INTERVAL



OVN.

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

HYDROGRAPH ROUTING

ROUTE HYDROGRAPH THROUGH LAKE PINE DAM

ISTAQ ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRI 0 INAME 1 IASTAGE 0 IAUTO 0  
LKPN 0  
ROUTING DATA  
QLOSS 0.000 AVG 0.00 IRES 1 ISAME 1 IOPT 0 IPMP 0 LSTR 0  
NSTPS 1 NSTOL 0 LAG 0 ANSKK 0.000 Y TSK STORA ISPRAT -1  
41.00 42.00 43.00 44.00 45.00 46.00 46.90 48.00 54.00  
FLOW 0.00 93.00 305.00 644.00 1022.00 1448.00 1544.00 1697.00 2094.00

SURFACE AREA= 0. 17. 46.

CAPACITY= 0. 45. 318.

ELEVATION= 33. 41. 50.

CREL 41.0 COOH 0.0 EXPH 0.0 EVEL 0.0 COOL 0.0 CAREA 0.0 EXPL 0.0

TOPEL 46.9 DAM DATA  
COGD 2.6 EXPD 1.5 DAMWID 140.

STATION LKPN, PLAN 1, RATIO 1

END-OF-PERIOD HYDROGRAPH ORIGINATES

MO.DA	HR.	IN	PERIOD	HOURS	INFLOW	OUTFLOW	STORAGE	STAGE
1	1	0	1	1	0	1	45	41.0
1	2	0	2	2	0	2	45	41.0
1	3	0	3	3	0	3	45	41.0
1	4	0	4	4	0	4	45	41.0
1	5	0	5	5	0	5	45	41.0
1	6	0	6	6	0	6	45	41.0
1	7	0	7	7	0	7	45	41.0
1	8	0	8	8	0	8	45	41.0
1	9	0	9	9	0	9	45	41.0
1	10	0	10	10	0	10	45	41.0
1	11	0	11	11	0	11	45	41.0
1	12	0	12	12	0	12	45	41.0
1	13	0	13	13	0	13	45	41.0
1	14	0	14	14	0	14	45	41.0
1	15	0	15	15	0	15	45	41.0
1	16	0	16	16	0	16	45	41.0
1	17	0	17	17	0	17	45	41.0
1	18	0	18	18	0	18	45	41.0
1	19	0	19	19	0	19	45	41.0
1	20	0	20	20	0	20	45	41.0
1	21	0	21	21	0	21	45	41.0
1	22	0	22	22	0	22	45	41.0
1	23	0	23	23	0	23	45	41.0
1	24	0	24	24	0	24	45	41.0
1	25	0	25	25	0	25	45	41.0
1	26	0	26	26	0	26	45	41.0
1	27	0	27	27	0	27	45	41.0
1	28	0	28	28	0	28	45	41.0
1	29	0	29	29	0	29	45	41.0
1	30	0	30	30	0	30	45	41.0
1	31	0	31	31	0	31	45	41.0
1	32	0	32	32	0	32	45	41.0
1	33	0	33	33	0	33	45	41.0
1	34	0	34	34	0	34	45	41.0
1	35	0	35	35	0	35	45	41.0
1	36	0	36	36	0	36	45	41.0
1	37	0	37	37	0	37	45	41.0
1	38	0	38	38	0	38	45	41.0
1	39	0	39	39	0	39	45	41.0
1	40	0	40	40	0	40	45	41.0
1	41	0	41	41	0	41	45	41.0
1	42	0	42	42	0	42	45	41.0
1	43	0	43	43	0	43	45	41.0
1	44	0	44	44	0	44	45	41.0
1	45	0	45	45	0	45	45	41.0
1	46	0	46	46	0	46	45	41.0
1	47	0	47	47	0	47	45	41.0
1	48	0	48	48	0	48	45	41.0
1	49	0	49	49	0	49	45	41.0
1	50	0	50	50	0	50	45	41.0
1	51	0	51	51	0	51	45	41.0
1	52	0	52	52	0	52	45	41.0
1	53	0	53	53	0	53	45	41.0
1	54	0	54	54	0	54	45	41.0
1	55	0	55	55	0	55	45	41.0
1	56	0	56	56	0	56	45	41.0
1	57	0	57	57	0	57	45	41.0
1	58	0	58	58	0	58	45	41.0
1	59	0	59	59	0	59	45	41.0
1	60	0	60	60	0	60	45	41.0
1	61	0	61	61	0	61	45	41.0
1	62	0	62	62	0	62	45	41.0
1	63	0	63	63	0	63	45	41.0
1	64	0	64	64	0	64	45	41.0
1	65	0	65	65	0	65	45	41.0
1	66	0	66	66	0	66	45	41.0
1	67	0	67	67	0	67	45	41.0
1	68	0	68	68	0	68	45	41.0
1	69	0	69	69	0	69	45	41.0
1	70	0	70	70	0	70	45	41.0
1	71	0	71	71	0	71	45	41.0
1	72	0	72	72	0	72	45	41.0
1	73	0	73	73	0	73	45	41.0
1	74	0	74	74	0	74	45	41.0
1	75	0	75	75	0	75	45	41.0
1	76	0	76	76	0	76	45	41.0
1	77	0	77	77	0	77	45	41.0
1	78	0	78	78	0	78	45	41.0
1	79	0	79	79	0	79	45	41.0
1	80	0	80	80	0	80	45	41.0
1	81	0	81	81	0	81	45	41.0
1	82	0	82	82	0	82	45	41.0
1	83	0	83	83	0	83	45	41.0
1	84	0	84	84	0	84	45	41.0
1	85	0	85	85	0	85	45	41.0
1	86	0	86	86	0	86	45	41.0
1	87	0	87	87	0	87	45	41.0
1	88	0	88	88	0	88	45	41.0
1	89	0	89	89	0	89	45	41.0
1	90	0	90	90	0	90	45	41.0
1	91	0	91	91	0	91	45	41.0
1	92	0	92	92	0	92	45	41.0
1	93	0	93	93	0	93	45	41.0
1	94	0	94	94	0	94	45	41.0
1	95	0	95	95	0	95	45	41.0
1	96	0	96	96	0	96	45	41.0
1	97	0	97	97	0	97	45	41.0
1	98	0	98	98	0	98	45	41.0
1	99	0	99	99	0	99	45	41.0
1	100	0	100	100	0	100	45	41.0













# BREAKNECK DAM SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

ELEVATION  
STORAGE  
OUTFLOW

INITIAL VALUE  
51.00  
122.  
2.

SPILLWAY CREST  
51.00  
122.  
2.

TOP OF DAM  
55.80  
354.  
1298.

RATIO  
OF  
PMF

.50

MAXIMUM  
RESERVOIR  
W.S.ELEV

56.38

MAXIMUM  
DEPTH  
OVER DAM

.58

MAXIMUM  
STORAGE  
AC-FT

388.

MAXIMUM  
OUTFLOW  
CFS

5717.

DURATION  
OVER TOP  
HOURS

1.64

TIME OF  
MAX OUTFLOW  
HOURS

21.00

TIME OF  
FAILURE  
HOURS

20.00

# LAKE PINE DAM SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....

ELEVATION  
STORAGE  
OUTFLOW

INITIAL VALUE  
41.00  
45.  
0.

SPILLWAY CREST  
41.00  
45.  
0.

TOP OF DAM  
46.00  
103.  
1544.

RATIO  
OF  
PMF

.50

MAXIMUM  
RESERVOIR  
W.S.ELEV

50.31

MAXIMUM  
DEPTH  
OVER DAM

3.41

MAXIMUM  
STORAGE  
AC-FT

332.

MAXIMUM  
OUTFLOW  
CFS

4165.

DURATION  
OVER TOP  
HOURS

20.00

TIME OF  
MAX OUTFLOW  
HOURS

22.00

TIME OF  
FAILURE  
HOURS

0.00



A4A3 I I I I I 1 I 144555EED I I I 144555AEED

A4A3 J J K K Y Y T V X K K Y T V X K K Y Y Y Y Y Y E E D K K K K Y Y Y Y Y Y E E E E K A A A A A

[illegible]



# CENTENNIAL LAKE DAM

## SUMMARY OF DAM SAFETY ANALYSIS

.....									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		59.60		59.60		65.00			
OUTFLOW		334.0.		334.0.		890.0.			
MAXIMUM		MAXIMUM		MAXIMUM		DURATION		TIME OF	
RESERVOIR		STORAGE		OUTFLOW		OVER TOP		MAX	
R.M.S.ELEV		AC-FT		CFS		HOURLS		HOURS	
OVER DAM									
		0.00		173.0.		0.00		40.00	
		0.00		313.0.		0.00		43.00	
		0.45		680.0.		19.00		33.00	
		.82		1033.0.		31.00		39.00	
		1.10		1357.0.		38.00		47.00	

# BEAVER CREEK DAM SUMMARY OF DAM SAFETY ANALYSIS

.....		ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	TIME OF MAX OUTFLOW	TIME OF FAILURE HOURS
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	MAX HOURS	HOURS
10	52.71	0.00	194.	426.	0.00	23.00	0.00
20	53.56	0.00	249.	873.	0.00	23.00	0.00
30	54.23	0.00	321.	1254.	0.00	24.00	0.00
40	55.77	0.97	413.	2024.	19.00	29.00	0.00
50	57.38	1.58	451.	2772.	25.00	27.00	0.00

STORCH ENGINEERS

Sheet \_\_\_\_\_ of \_\_\_\_\_

Project BREAKNECK DAM


\* 1132

Made By EAW Date APR 17, 1977

% PMF PASSED THROUGH SPILLWAY

Chkd By \_\_\_\_\_

Date \_\_\_\_\_



STORCH ENGINEERS

Sheet \_\_\_\_\_ of \_\_\_\_\_

Project BREAKNECK DAM

# 1122

Made By EAW Date APR. 17, 1977

STAGE VS. TIME (LAKE PINE - DOWNSTREAM)

Chkd By \_\_\_\_\_

Date \_\_\_\_\_


WATER SURFACE ELEV. IN LAKE PINE VS. STORM TIME

(DOWNSTREAM FROM BREAKNECK DAM)

— OVERTOPPING AT BREAKNECK DAM

---- BREACH AT BREAKNECK DAM

WATER SURFACE ELEV. LAKE PINE (FT. MSL)



NOTE:

THIS ANALYSIS ASSUMES THAT LAKE PINE DAM DOES NOT BREACH. CONSERVATIVE DOWNSTREAM STAGE.

APPENDIX 5

Bibliography



1. "Recommended Guidelines for Safety Inspection of Dams," Department of the Army, Office of the Chief of Engineers, Washington, D. C. 20314.
2. Design of Small Dams, Second Edition, United States Department of the Interior, Bureau of Reclamation, United States Government Printing Office, Washington, 1973.
3. Holman, William W. and Jumikis, Alfreds R., Engineering Soil Survey of New Jersey, Report No. 19 Monmouth County, Rutgers University, New Brunswick, N. J. 19545.
4. "Geologic Map of New Jersey" prepared by J. Volney Lewis and Henry B. Kummel, Dated 1910 - 1912.
5. Stankowski, Stephen J., Magnitude and Frequency of Floods in New Jersey with Effects of Urbanization, Special Report 38, State of New Jersey Department of Environmental Protection. Division of Water Resources, 1974.
6. Herr, Lester A., Hydraulic Charts for the Selection of Highway Culverts, U. S. Department of Transportation, Federal Highway Administration, 1965.
7. Safety of Small Dams, Proceedings of the Engineering Foundation Conference, America Society of Civil Engineers, 1974.
8. King, Horace Williams and Brater, Ernest F., Handbook of Hydraulics, Fifth Edition, McGraw-Hill Book Company, 1963.
9. Davis, Calvin Victor, (Ed.), Handbook of Applied Hydraulics, Second Edition, McGraw-Hill Book Company, 1952.
10. Clark, C. O., "Storage and The Unit Hydrograph" Paper No. 2261, Transactions, American Society of Civil Engineers, 1945.

11. The following plan, section and detail drawings prepared by Albert C. Jones, PE:

Plan View and Section, Breakneck Dam (no date) Approved February 3, 1941.

Detail and Section Views, Proposed Reinforced Concrete Strut (no date) Approved February 3, 1941.

